WEBEL TECHNOLOGY LIMITED

NOTICE INVITING e-TENDER

e-Tender are invited for implementation of Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal. Bids are invited from reputed System Integrators having sufficient experience and credentials for successful completion of "Similar Nature" of work in a Central or State Government Department/PSU/Autonomous Body. WTL has been chosen as the execution authority for the same. Bidder must have adequate Service Engineer for providing on-site support service within the stipulated time as prevalent for IP Based CCTV System setups.

1.	Tender No. & Date	WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026
2.	Tender Version No.	1.0
3.	Brief description of material	Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal
4.	Tender Fee	Rs.6000 (Rs Six Thousand only). The amount to be transferred online through e-tender portal.
5.	Earnest Money Deposit	Rs. 16,00,000.00 (Sixteen Lacs Only). The amount to be transferred online through e-tender portal.
6.	Date of Downloading	01-09-2026
7.	Pre-Bid Meeting date & time	08-09-2026 at 4 PM. (Online) • Pre-Bid meeting will be organized in online platform only. • Only queries as per format (Section - N) reaching WTL by 07-09-26 at 3 PM. will be taken for decision. • Interest bidders are requested to send mail to purchase@wtl.co.in for participation of online pre-bid meeting. Based on request WTL will share meeting id / links for meeting. If there is any change in date and time, then will inform.
8.	Bid Submission Start date & time	15-09-2026 at 2 PM
9.	Last date & time of EMD & Tender Fee submission intimation.	Before Uploading of Tender
10.	Last date & time of Bid Submission	22-09-2026 at 2 PM
11.	Date & time of Technical Bid Opening	24-09-2026 at 2 PM
12.	WTL Address	WEBEL TECHNOLOGY LIMITED (A Govt. of West Bengal Undertaking) Plot - 5, Block – BP, Sector – V, Salt Lake City, Kolkata – 700091.
13.	Contact person	033-23673403-06

WEBEL TECHNOLOGY LIMITED

1. Intending bidder may download the tender documents from the website **https://wbtenders.gov.in** directly with the help of Digital Signature Certificate. Necessary Tender fee may be remitted online through e-tender portal in favour of "Webel Technology Limited" and also to be documented through e-filling. Necessary Earnest Money Deposit (EMD) may be remitted online through e-tender portal in favour of "Webel Technology Limited" and also to be documented through e-filling.

2. Both Techno Commercial Bid and Financial Bid are to be submitted concurrently duly digitally signed in the website **https://wbtenders.gov.in**.

3. Tender documents may be downloaded from website and submission of Techno Commercial Bid and Financial Bid will be done as per Time Schedule stated in Section – C of this Tender Document.

4. The Financial Bid of the prospective Bidder will be considered only if the Techno Commercial Bid of the bidder is found qualified by the Tender Committee. The decision of the 'Tender Committee' will be final and absolute in this respect. The list of Qualified Bidders will be displayed in the website.

5. All clarifications / corrigenda will be published only on the **https://wbtenders.gov.in.**

WEBEL TECHNOLOGY LIMITED

CONTENTS OF THE TENDER DOCUMENT

The Tender document comprises of the following:

SECTION – A	BACKGROUD & OBJECTIVE OF THE PROJECT
SECTION – B	SCOPE OF WORK
SECTION – C	DATE AND TIME SCHEDULE
SECTION – D	BIDDER'S ELIGIBILITY CRITERIA
SECTION – E	INSTRUCTION TO BIDDER
SECTION – F	BID FORM
SECTION – G	TECHNO COMMERCIAL EVALUATION & AWARDING OF CONTRACT
SECTION – H	GUIDANCE FOR E-TENDERING
SECTION – I	UN-PRICE BILL OF MATERIAL
SECTION – J	DETAILS OF TECHNICAL CAPABILITY OF BIDDER
SECTION – K	FINANCIAL CAPABILITY OF BIDDER
SECTION – L	BIDDER'S DETAILS
SECTION – M	FORMAT FOR PRE-BID MEETING QUERY
SECTION – N	LIST OF CLIENTS OF SIMILAR ORDERS
SECTION – O	PROFORMA FOR PERFORMANCE BANK GUARANTEE
SECTION – P	NIT DECLARATION
SECTION – Q	MAKE, MODEL & PART NUMBER DECLARATION
SECTION – R	TECHNICAL SPECIFICATION COMPLIANCE STATEMENT
SECTION – S	MANUFACTURER'S AUTHORIZATION FORM
SECTION – T	CHECKLIST FOR ELIGIBILITY CRITERIA

WEBEL TECHNOLOGY LIMITED

SECTION – A

PROJECT OBJECTIVE

1. PROJECT OBJECTIVE

CCTV Surveillance Project with Night Vision Surveillance Camera & ANPR Camera Integration for Chicken Neck (Siliguri Corridor) & International Border Areas under IGP, North Bengal.

The objective of the proposed project is to design, supply, install, commission, and operationalize an integrated, state-of-the-art CCTV surveillance system incorporating Automatic Number Plate Recognition (ANPR) cameras and high-resolution bullet cameras across the strategically sensitive Chicken Neck (Siliguri Corridor) region and adjoining international border areas under the jurisdiction of the Inspector General of Police (IGP), North Bengal.

The project aims to enhance situational awareness, strengthen border and internal security, support intelligence-led policing, and enable real-time monitoring of vehicular and human movement across critical locations in the Police Districts of Darjeeling, Jalpaiguri, Cooch Behar, Alipurduar, Malda, Islampur, Raiganj, Dakshin Dinajpur and Siliguri Police Commissionerate.

2. Specific Objective

2.1 Strengthening Border and Internal Security

- To monitor vulnerable border stretches, transit routes, and infiltration-prone zones
- To deter and detect illegal cross-border activities including smuggling, trafficking, and unlawful migration
- To assist security forces in maintaining territorial integrity

2.2 Intelligent Vehicular Monitoring through ANPR

- To automatically capture and recognize vehicle registration numbers in real time
- To create a searchable database of vehicle movement across districts
- To detect stolen, suspicious, or blacklisted vehicles
- To support enforcement of traffic regulations and investigation of criminal activities

2.3 Comprehensive Area Surveillance

- To provide continuous visual coverage of strategic and high-risk locations including highways, junctions, entry/exit points, border approach roads, marketplaces, and public spaces
- To enhance monitoring during large gatherings, festivals, and emergencies

2.4 Real-Time Monitoring and Rapid Response

- To enable centralized monitoring from designated District police control rooms
- To facilitate prompt decision-making and deployment of field units
- To improve emergency response capability

2.5 Crime Prevention, Detection, and Investigation

- To deter criminal activities through visible surveillance
- To provide admissible digital evidence for investigation and prosecution
- To assist in post-incident analysis and reconstruction

2.6 Inter-District Coordination

- To establish a unified surveillance network enabling seamless sharing of video feeds and data among multiple police districts
- To track movement of suspects across administrative boundaries

2.7 Enhancement of Public Safety

- To improve overall law-and-order management
- To increase citizens' sense of security in sensitive and high-traffic areas

2.8 Conclusion

The proposed CCTV Surveillance Project with ANPR integration is envisaged as a critical security infrastructure initiative for North Bengal. By deploying advanced surveillance technologies across multiple districts within the Chicken Neck region and international border areas, the project will significantly augment the capability of law enforcement agencies to safeguard national interests, maintain public order, and ensure the safety of citizens.

3. About WTL

Webel Technology Ltd, a Govt. of West Bengal Undertaking under the Department of PAR is designated as the state nodal agency for delivery of e-Governance Solutions for the Government of West Bengal. WTL is a certified agency for ISO 9001:2015, ISO/IEC 27001:2013 and CMMI Level 5 certified for delivery of e-Governance services and infrastructure projects. The Governor of West Bengal has authorized WTL both as The State Nodal Agency (SNA) & State Implementing Agency (SIA) for all e-Governance related activities in the State.

WTL was incorporated in April 2001 and has been profitable since inception. Since the last five years, WTL has undertaken the most challenging projects envisaged by the Government and is one of the fastest growing Government Undertakings. WTL has on behalf of the State Government in all its major e-Governance initiatives such as:

- WBSWAN - MPLS-VPN connectivity up to Block levels,
- Integrated Financial Management System,
- e-Recruitment initiatives,
- e-Reservation for various State Transport Corporations,
- e-Registration of Land Deeds,
- e-Governance initiatives of the Directorate of Commercial Taxes (e-Registration, e-Amendment, e- Payment, e-Return, e-Refund, e-Appeal, e-Forms, e-STDS & DMS).
- Digitization of all legacy Land records and Modernization of Record Rooms up to Block level and
- Implementation of Incident Response System along with setting up of State-of-the-art Emergency Operation Centre for the Department of Disaster Management etc.

SECTION – B

SCOPE OF WORK

1. Detailed Scope Of Work For Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal.

1. **Supply of Equipment**

- IP-Based Cameras for total Surveillance as it required.
- Network Video Recorders for seamlessly integrate and connect the IP Cameras.
- Hard Disk Drives for storing of Enormous amount of Data feeds from IP Cameras.
- Rugged Outdoor Cabinets with weatherproof housing for storing Fan, PDU and other Accessories.
- Network Switch (PoE) for connectivity of the surveillance system.
- Mounting Accessories, Display, Uninterrupted Power Supply with Battery, Power Supply & Hardware including clamps, brackets, and poles where new installation is needed.

2. Installation and Commissioning

- Site Survey to identify strategic areas, zones for effective implement of Camera positions.
- Installation & Mounting ensuring maximum enhancement with minimal deviation in the environments. All the CCTV will be installed within the existing CCTV if any.
- Network (Broadband with static IP) Integration with surveillance field switches or extending feed to the central control room as required.
- Configuration of CCTVs, enabling selective or broadcast-wide messaging from the central control room.
- Testing of all equipment and system capabilities.

3. Training and Handover

- Training Sessions for Officials and command center staff on operating the IP Based CCTV system through software.
- User Manuals & SOPs covering common operations like emergency broadcasting, scheduling messages, and system health monitoring.
- Handover of Complete System Documentation including network diagrams, configuration backups, and hardware inventory.

Conclusion

The proposed CCTV Surveillance Project with ANPR integration is envisaged as a critical security infrastructure initiative for North Bengal. By deploying advanced surveillance technologies across multiple districts within the Chicken Neck region and international border areas, the project will significantly augment the capability of law enforcement agencies to safeguard national interests, maintain public order, and ensure the safety of citizens.

End of Life (EOL)

The OEM of IP Based CCTV System should declare that no offered products will be EOL in next 7 years. A letter of Confirmation by OEM shall be mandatory during tender process. During the Comprehensive warranty period of 3 years (CCTV only), no other active component / accessories should be declared End of Life. In case it is declared "End of Life" during this period, the vendor has to replace such equipment at their own cost.

Provision for Extended Warranty (Beyond 3 Years)

The project includes an optional provision for extended warranty support beyond the initial 3-year comprehensive warranty period. This extended warranty shall cover maintenance, servicing, replacement of defective parts, and on-site technical support for an additional period as required by the client (typically up to 5 years in total).

SI Partner Selection

The WTL Project manager shall be responsible for the preparation of the detailed tender document for the SI partner selection.

- Eligibility & Technical Compliance.
- Price Bid

The tender document shall consist of the following:

- **Partner/SI eligibility Criteria**
  - Minimum financial eligibility criteria, including turnover requirement, profitability, net worth of company for last 3 years
  - Technical Capability to implement project, prior experience of successfully completed one or more IT/ITES infrastructure and services, adding up to the bid value of the present project.
  - Support Capability of partner, proof of presence in West Bengal for last 5 years, with service network.
  - Credibility criteria of not having been blacklisted by any Government or PSU in India in the last 3 years.
  - OEM Eligibility Criteria - for items/equipment to be supplied by SI partner.
  - Preference to Make in India for items manufactured in India. Only the Manufacturers, who are manufacturing CCTV equipment for minimum 3 years are eligible. (With respect to last date of submission of bid). Certificate issued by the Competent Authority of the Government in support of existence of their manufacturing unit of CCTV equipment since last 3 years, Registration Certificate wherein the nature of business is indicated
  - Primary OEMs – Camera/Storage OEMs must have manufacturing presence in India and service/repair center in Kolkata.
  - OEMs OEM should not have been blacklisted by any Government Organization in India or Globally
  - The OEM for Camera should not have been blacklisted or banned or support suspended by ONVIF

Evaluation process

The tender shall be evaluated in 3 steps, as per the process set. As this tender shall be for selection of SI partner and solution from OEMs as per the set technical specifications, the process shall be kept simple, based on Eligibility, Technical Compliance and Price bid. The technically eligible bidders' price bids shall be opened and the L1 bidder shall be awarded the contract. The following are key steps of the tender evaluation process:

Tender Eligibility of Bidder – The bidders' eligibility to participate in the tender, based on the technical experience, Project implementation experience, Services and Support infrastructure in West Bengal, Financial capability shall be considered for eligibility. Additional eligibility criteria may be part of the tender, based on the inputs of the tender committee. Bidders meeting the Eligibility criteria for the tender shall be considered for technical evaluation.

Technical Evaluation – The technical evaluation shall be conducted by a technical sub-committee appointed by the "Tender Committee". The technical evaluation shall be based on the following broad criteria:

Adherence to the specifications for Active and Passive Components specified in the BOQ and technical specifications of each equipment.

Manufacturers' Authorization (MAF) for the bidder to supply the equipment from the OEM.

OEM eligibility for the item quoted, as per the OEM eligibility terms and conditions specified in the tender. All OEMs of primary equipment, such as IP CCTV, Software, Network Switch, Network Cables etc. must meet the eligibility criteria set in the tender.

The technical subcommittee shall evaluate each technical bid, and evaluate the technical compliance for each item in the BoQ/BoM for the tender, and submit the same to Tender committee for final decision.

All technically compliant bids shall be eligible for price bid opening.

The technically eligible bidders, based on technical evaluation and compliance summary shall be called for "Price Bid" opening. The Price Bid of the L1 bidder, based on compliance to all priced items as per the BoQ/BOM, shall be awarded the partnership contract for the project implementation.

Project Implementation Process

The project implementation process to be followed shall include the selected Project Implementation Partner (SI) process for the timely installation of the IP Based CCTV System and other equipment, including passive and active components at site. The SI partner shall also setup the support call center for immediate support services as part of the process. The following are the steps of the process to be followed.

1. Conducting of Site Survey as per plan
    a. Submit site survey report with detailed diagram for each IP CCTVs.
    b. Submit list of equipment to be delivered and installed at each site.

2. Supply and installation at site.
    a. Supply the listed items as per BOQ for each site approved.
    b. Install the equipment (Active/Passive) and other site work as per plan.

c. Install the Software and demonstrate the functioning of the site. Update software with the CCTV Location identification number for easy tracking.
d. Update the installation database for future reference and support requirement.

3. Setup Support Service location (Kolkata) for reporting of issues/problems from site.
   a. Provision trained manpower for support
   b. Provision for infrastructure and Support call tracking, issue tracking, assignment of calls to field, status up-dation of repair/replacement.
   c. Reporting of support status on monthly basis as per SLA.

4. Setup field support center
   a) SI partner must provision for support center in West Bengal.
   b) Maintain adequate spares for BOQ items as inventory for replacement of faulty product within 48 / 72 hours of reporting of issue.
   e. Maintain centralized spare inventory for components, such as CCTV, Switch, for replacement within 72 hours of reporting any fault.

The SI implementation partner shall be required to perform the implementation work as per the agreed implementation plan approved by the PMU. The details of the services to be provided and the SLAs shall be finalized by WBP and WTL PMU.

District Wise Camera Installation Location Details

ALIPURDWAR POLICE DISTRICT					
SL NO	**LOCATION NAME**	**LATITUDE**	**LONGITUDE**	**ANPR CAMERA**	**BULLET CAMERA**
1	Super Market More Inter National Border with Bhutan	26.8566	89.3814	2	4
2	ITI More Alipurduar Border with Cooch Behar	26.4782	89.509	2	3
3	Barobisha Parigiri Border With Assam	26.4539	89.8419	2	3
4	GST More	26.8124	89.3725	2	3
5	Ethelbari More Border with Jalpaiguri	26.7054	89.0732	2	3
6	Dulal Dokan Near Durga Mandir Eith Ghoksadanga	26.5148	89.2121	2	3
7	Sonapur Chowpathy Border with Cooch Behar	26.4936	89.3685	2	3
8	Dodua Bridge Border with Jalpaiguri	26.5453	89.1113	2	2
		TOTAL		**16**	**24**

DAKSHIN DINAJPUR POLICE DISTRICT					
SL NO	**Location Name**	**Latitude**	**Longitude**	**ANPR CAMERA**	**BULLET CAMERA**
1	Trimohini & Pagliganj More	25.282724	88.940727	2	4
2	Patiram Roler More	25.323902	88.761749	2	4
3	Laskar Haat	25.220271	88.577375	2	4
4	Danogram	25.323921	88.260485	2	4
5	Fulbari	25.370372	88.603731	2	3
6	Balurghat Bus Stand	25.226317	88.78186		8
7	Kamarpara	25.249767	88.862487	2	4
8	Gangarampur Chowpati	25.406105	88.517892	2	3
9	Dutta Para More	25.405507	88.521873		8
		TOTAL		**14**	**42**

ISLAMPUR POLICE DISTRICT					
SL NO	**LOCATION NAME**	**Latitude**	**Longitude**	**ANPR CAMERA**	**BULLET CAMERA**
1	Oil India More On Nh 31	26.44311	88.259248		8
2	Basta Dangi Naka Point	25.922691	87.838053	2	4
3	Balichukka	26.1183389	87.9792747	2	4
4	Chargharia More	26.036662	88.070706	2	4
5	Shrikrishnapur	26.279847	88.21918		8
6	Nawab Chawk & Sarrounding More	26.2630717	88.1856164		8
7	Bihar More On Nh 31, Sonapur	26.432664	88.265025		8
8	Tinmile Road On Nh 31 & Sarrounding Junction	26.409808	88.27808		8
9	Purnia More	25.887896	87.82374	2	4
10	Kanki Bus Stand	26.007753	87.857764		8
11	Asuraghar	25.961916	87.848752		8
12	Aligang Bypass More	26.2369507	88.1582709		8
		TOTAL		**8**	**80**

RAIGANJ POLICE DISTRICT					
SL NO	**Location Name**	**Latitude**	**Longitude**	**ANPR CAMERA**	**BULLET CAMERA**
1	Maharaja Hat	25.7090921	88.1151042		8
2	Uttar Goal Para (Kaichdangi) Tinmatha More	25.5997543	88.1333819		8
3	Under Rupahar Overbridge	25.571079	88.1326636		8
4	Dhankoil Maheshpur More	25.625595	88.3457		8
5	Old Bus Stand	25.678147	88.214433		8
6	Machol Bihar Entry Point	25.7362654	87.9859113		8
7	Jharbari More	25.79104	87.92601		8
8	Itahar Chowrasta More - Anpr	25.45452	88.173621	4	
9	Itahar Chowrasta More - Cctv	25.454491	88.1738883		8
10	Balarampur Bihar Border Naka	25.76118	87.95777		8
11	Kasba Netaji More	25.588825	88.129702	2	3
12	Vivekananda More	25.639209	88.3245085	2	3
13	Thakurbari More	25.772195	88.210788	2	2
		TOTAL		**10**	**80**

MALDA POLICE DISTRICT					
SL NO	**LOCATION NAME**	**LATITUDE**	**LONGITUDE**	**ANPR CAMERA**	**BULLET CAMERA**
1	Bhutni Bridge Naka point	25.12064	87.87508	2	4
2	Pukhuria More	25.11736	88.001812	2	4
3	Gitamore Durga Mandir More	24.977818	88.034345	2	4
4	Saranpara Inter jurisdiction boarder with Banshihari Police Station & Harirampur Police Station	25.295622	88.302201	2	3
5	Adina Stand	25.15185	88.165177		8
6	Bamangola Naka Point	25.1687	88.337002	2	2
7	Bhabanipur Bridge	25.448939	87.906869		8
8	Mathurapur Chowrangi Morh	25.111916	87.8964089		8
9	Nurpur Bridge	25.164937	87.937223	2	4
10	Kanir More	24.984216	88.137029		8
11	Badhapukur More	24.994656	88.143991	2	4
12	Sujapur More	24.91126	88.086839	2	4
13	Jalalpur More	24.893749	88.069349		8
14	Matal More near New Farakka Bridge Gate	24.80894	87.95113		8
15	Jhanjra More – CCTV	25.027561	88.160932		8
16	Jhanjra More – ANPR	25.029166	88.1602566	2	2
17	12 Mile Stand Naka Check Post	25.101605	88.364567	2	4
18	Bidroho More	25.21367	88.1942317		8

19	Kushida Bus Stand	25.532866	87.94974		8
		TOTAL		**20**	**107**

KALIMPONG POLICE DISTRICT

SL NO	LOCATION NAME	LATITUDE	LONGITUDE	ANPR CAMERA	BULLET CAMERA
1	Chitrey Fatak	27.065502	88.428336	2	3
2	Reang Ps	26.984791	88.41666	2	3
3	Pandara	27.064625	88.659054	2	2
4	Mongpong Adpc	26.882473	88.48864		8
5	Sadobatey	27.0643577	88.4696375		8
6	Lava Bazar	27.084964	88.665628		8
7	Kumani More	26.969258	88.856213		8
8	Naxal Bridge Fatak	27.008927	88.868413		8
9	Rangpo Check Post	27.1699488	88.5259411	2	2
		TOTAL		**8**	**50**

COOCHBEHAR POLICE DISTRICT

SL NO	LOCATION NAME	LATITUDE	LONGITUDE	ANPR CAMERA	BULLET CAMERA
1	Chengrabandha VIP More	26.41511	88.918803	2	4
2	Mirgipur Naka Point	26.344893	88.924965	2	3
3	Kaljani Bridge	26.24977	89.609879	2	3
4	Jorai More	26.312416	89.750903	2	4
5	Mansai Assam - Bengal Border	26.266041	89.716794	2	3
6	Balabhut Bridge Naka	26.218763	89.6953269	2	4
7	Torsa Bridge at Ghughumari	26.285752	89.459086	2	4
8	Dinhata Chowpathy	26.127975	89.4630939		8
9	Sankosh Bridge	26.460255	89.8509657	2	4
10	Darla Bridge Conecting Mathabanga	26.273712	89.203827	2	2
11	UBKV More	26.40446	89.383135		8
12	Khagrabari Chowpathi	26.345428	89.447986		8
13	Chakchaka Intersection	26.324214	89.48168		8
14	Ghughumari Chowpathi	26.283646	89.4593451		8
15	Bochamari Chowpathi	26.404407	89.7218177		8
16	Kadmtala Bazer in Pundibari	26.432815	89.37476	2	3
17	Gosanimari Chowpathi	26.140331	89.3595586		8
		TOTAL		**20**	**90**

DARJEELING POLICE DISTRICT					
SL NO	**LOCATION NAME**	**LATITUDE**	**LONGITUDE**	**ANPR CAMERA**	**BULLET CAMERA**
1	Muraliganj Naka Point	26.466228	88.235508	2	4
2	Ghoshpukur Traffic More - CCTV	26.592558	88.287954		8
3	Chekarmari Bazar	26.528651	88.145436	2	4
3	Rathkhola More	26.673101	88.195068	2	4
5	Rohini More	26.801207	88.3064851	2	4
6	Shivam Hotel Flyover	26.64716	88.17554	2	4
7	Md. Box Traffic More	26.643025	88.371547	2	4
8	Alay More	26.881828	88.18877		8
9	Kurseong Railway Station	26.877953	88.277744		8
10	Kadma More	26.756302	88.239494		8
11	Zone 1(Jb Ps)	27.008203	88.25959		8
12	Zone 3 (Jb Ps)	27.008276	88.254254		8
13	Singmari Fatak	27.060884	88.252509		8
13	Below Forest	27.033308	88.258264		8
15	Ghoshpukur Traffic More - Anpr	26.59244	88.2875375	4	
		TOTAL		**16**	**88**

JALPAIGURI POLICE DISTRICT					
SL NO	**LOCATION NAME**	**LATUTUDE**	**LONGITUDE**	**ANPR CAMERA**	**BULLET CAMERA**
1	Deomali on AH-48	26.634449	89.028956	2	4
2	Balapara	26.559834	88.732616		8
3	Maynaguri PS Indira More on NH-31D	26.55221	88.824158	2	4
4	Hati More on NH-31D	26.582318	88.512865		8
5	Gazoldoba 10 No	26.763284	88.606696		8
6	Moraghat on NH-31C	26.769216	89.035714	2	4
7	Oodlabari Chowpathy on NH-31C	26.865443	88.624551	2	4
8	Rangdhamali	26.613815	88.66801		8
		TOTAL		**8**	**48**

SILIGURI POLICE COMMISSIONERATE					
SL NO	**Location Name**	**Latitude**	**Longitude**	**ANPR CAMERA**	**BULLET CAMERA**
1	In front of Desun Hospital	26.6859	88.39686	2	2
2	TCP More	26.75937	88.34025	2	2
3	Canal road near Canal road STG	26.66194	88.47039	2	2
4	Dumping ground more	26.74567	88.45379	2	2
		TOTAL		**8**	**8**

District Wise Camera Qty. Distribution			
SL NO	**LOCATION NAME**	**ANPR CAMERA**	**BULLET CAMERA**
1	Alipurduar	16	24
2	Cooch Behar	20	90
3	Jalpaiguri	8	48
4	Darjeeling	16	88
5	Kalimpong	8	50
6	Islampure	8	80
7	Raiganj	10	80
8	Dakshin Dinajpur	14	42
9	Malda	20	107
10	Siliguri	8	8
		128	**617**

Repair Center

Repair center will be available from CCTV OEMs in Siliguri for rectification of faults and will ensure. Repair center must complete proper repair and send back the item within 7 days to ensure healthy stock status, as part of SLA. In case of any delay, the OEM must arrange for replacement of the faulty item.

Service & Support Infrastructure Setup in Siliguri, West Bengal (preferred)

The successful bidder (contractor) shall have the required services and support setup, with qualified manpower and adequate spares to ensure delivery of the support services as per the SLA required, within Kolkata. Details of existing setup, manpower and location, must be provided with documentary proof, for the purpose of technical evaluation of bid.

The Scope Work of WBP for this Project:

1) Smooth integration permission, access of existing network terminals within the existing racks/ JB/Poles/UPS Power of CCTV system of WBP.
2) Uninterrupted network at every CCTV location (High Speed Broadband Connection with dedicated Public / Static IP address from ISP.)
3) UPS (Uninterrupted Power Source AC 220V) at Network Rack.
4) Space within the outdoor network rack / JB for Network Switch and PDU / Power supply installation.
5) 1 No. Copper network terminal (LAN Port) of broadband connection at each location's outdoor network rack.
6) Permission of road cutting & overhead cabling (if required).
7) Permission of all existing Electrical / traffic signal or blinker poles for camera / rack installation and cable laying.
8) Communication, vehicle support for remote location from district HQ and approvals from other stake holders for execution work.
9) Distribution of Body Worn Camera and Night Vision Binocular to the respective district.

WEBEL TECHNOLOGY LIMITED

SECTION – C

DATE AND TIME SCHEDULE

Sl. No.	Particulars	Date & Time
1	Date of uploading of N.I.T. & other Documents	01-09-26
2	Documents download start date	01-09-26
3	Pre-Bid Meeting (On Line)	08-09-26 at 4 PM
4	Bid Submission start date & time (On line)	15-09-26
5	Bid Submission closing date & time (On line)	22-09-26
6	Bid opening date & time for Technical Proposals (Online)	24-09-26

WEBEL TECHNOLOGY LIMITED

SECTION – D

BIDDER'S ELIGIBILITY CRITERIA

1. The bidder must be a company registered under Companies Act, 1956/2013 or Partnership or LLP or OPC or Proprietary Firm. Documentary (Certificate of incorporation/Relevant document) evidence to be submitted.

2. The bidder must be a System Integrator in IT/ITS, Networking Sector or Audio Video sector. Relevant document to be submitted.

3. The bidder should have been operating for the last 5 years in India. Certificate of Incorporation and/ or Certificate of Commencement of Business issued by the Registrar of Companies/ Partnership Registration/ sole proprietorship registration under the Shops & Establishments Act to be submitted.

4. The bidder must have their Registered/ Branch office in West Bengal. Valid trade license and local GST Registration Certificate are to be submitted

5. The bidder should have valid GST Registration Certificate & PAN. Bidder shall have to submit photocopy of the documents.

6. Bidder should have own support service / call booking number (Undertaking letter should be submitted from the bidders) OEM support service number will not be treated as bidder's support service number. Support service number details for bidder with number & detailed to be submitted. Bidder shall have to submit the Complain/Call escalation matrix in their own letterhead with undertaking.

7. The bidder shall have executed "Similar Nature" of **single order an amount** not less than **Rs. 6.40 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided.

   OR

   The bidder shall have executed "Similar Nature" of **two orders, each amount** not less than **Rs. 4.00 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided.

   .

   OR

   The bidder shall have executed "Similar Nature" of **three orders, each amount** not less than **Rs. 3.20 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided.

8. The bidder should have a minimum **average annual turnover** of not less than Rs. **12.00 Crore** in the last three financial year (2022-23. 2023-24, 2024-25). Bidder shall have to submit Audited Balance Sheet / Audited Accounts / Auditor Certificate in support of their claim.

9. Bidder should have Positive net worth for last three financial years (2022-23. 2023-24, 2024-25). Bidder shall have to submit Audited Balance Sheet / Audited Accounts / Auditor Certificate in support of their claim.

10. The bidder should have ISO certification of ISO 9001:2015. Certificate to be submitted.

11. The bidder must submit the Manufacturers Authentication Form (MAF) for IP Based CCTV, Networking Switches & Network Passive component as per prescribed format enclosed (Section - S).

12. Technical Compliance statements to be submitted. Without these documents from the OEMs, the offer will be treated as non-responsive and summarily rejected.

13. The bidder shall submit Bid Form (Section – E) duly signed by the authorized signatory of the company as per the format enclosed. Deviation in format may not be accepted.

14. Bidder shall submit NIT Declaration (Section – O) duly signed by the authorized signatory of the company as per the format. Deviation in format may not be accepted.

15. The bidder shall not have been blacklisted by any State/Central Government or PSU Organization or bilateral/multilateral funding agencies for breach of ethical conduct or fraudulent practices as on date of submission of the proposal (as per DIT guidance note issued on 26-Dec-2011). Declaration on bidder's letter head to be submitted.

WEBEL TECHNOLOGY LIMITED

SECTION – E

INSTRUCTIONS TO BIDDER

1. DEFINITIONS

In this document, the following terms shall have following respective meanings:

"**Agreement**" means the Agreement to be signed between the successful bidder and WTL including all attachments, appendices, all documents incorporated by reference thereto together with any subsequent modifications, the RFP, the bid offer, the acceptance and all related correspondences, clarifications, presentations.

"**Acceptance Test Document"** means a document, which defines procedures for testing the functioning of installed system. The document will be finalized with the contractor within 7 days of issuance of the Letter of Award.

"**Bidder**" means any firm offering the solution(s), service(s) and /or materials required in the RFP. The word Bidder when used in the pre award period shall be synonymous with Bidder, and when used after award of the Contract shall mean the successful Bidder.

"**Contract**" is used synonymously with Agreement.

"**Contract Price"** means the price to be paid to the Contractor for providing the Solution, in accordance with the payment terms.

"**Contractor**" means the Bidder whose bid to perform the Contract has been accepted by Tender Committee and is named as such in the Letter of Award.

"**Default Notice**" mean the written notice of Default of the Agreement issued by one Party to the other.

"Installation" means installation of supplied Hardware & Software.

"**Fraudulent Practice**" means a misrepresentation of facts in order to influence a procurement process or the execution of a Contract and includes collusive practice among Bidders (prior to or after Bid submission) designed to establish Bid prices at artificial noncompetitive levels and to deprive WTL and eventually Departments of Gov. of W. Bengal of the benefits of free and open competition.

"**GoI**" shall stand for the Government of India.

"**GoWB**" means Government of West Bengal.

"Personnel" means persons hired by the Bidder as employees and assigned to the performance of the Infrastructure Solution or any part thereof.

"**Similar Nature of Work"** means Works entailing completion of a project in the field of Networking / CCTV / Integrated Surveillance system / Large IT Infrastructure work for any Govt. Departments or Public Sector Undertakings.

"Project" Supply, Installation, Testing, Commissioning with 3 (three) years Warranty & Comprehensive Maintenance of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular (both with 1 Year Warranty) under Inspector General of Police (North Bengal Region), West Bengal

"Services" means the work to be performed by the Bidder pursuant to this Contract, as described in the detailed Scope of Work.

"**Interest rate**" means "364 days Government of India (GoI) Treasury Bills" rate.

"**Law**" shall mean any Act, notification, bye law, rules and regulations, directive, ordinance, order or instruction having the force of law enacted or issued by the Central Government and/or the Government of West Bengal or any other Government or regulatory authority or political subdivision of government agency.

"LOI" means issuing of Letter of Intent shall constitute the intention of the WTL to place the Purchase Order with the successful bidder.

"**Requirements**" shall mean and include schedules, details, description, statement of technical data, performance characteristics, standards (Indian as well as International) as applicable and specified in the Contract.

"Service" means provision of Contracted service viz., operation, maintenance and associated services for DEPLOYED SYSTEMS along with centralized dashboard as per Section titled "Scope of Work".

"Termination Notice" means the written notice of termination of the Agreement issued by WTL.

"Uptime" means the time period when specified services are available with specified technical and service standards as mentioned in section titled WARRANTY SUPPORT" **"%Uptime"** means ratio of 'up time' (in minutes) as mentioned in section titled "Warranty support".

"**Service Down Time**" (SDT) means the time period when specified services with specified technical and operational requirements as mentioned in section titled "WARRANTY SUPPORT"" are not available to Gov. of W. Bengal and its user departments and organizations.

"WTL" means Webel Technology Limited a Govt. of West Bengal undertaking.

2. PRE BID MEETING

Pre Bid Meeting will be held on 08-09-26 at 4 PM (On-Line Meeting). Bidder can send their queries as per format (Section - L) to Purchase Department (purchase@wtl.co.in). Only the queries received within the stipulated date prior to the Pre Bid Meeting will be answered. Interest bidders are requested to send mail to (purchase@wtl.co.in) for participation of online pre-bid meeting. Based on request WTL will share meeting id / links for meeting. If there is any change in date and time then will inform.

3. COST OF BIDDING

The bidder shall bear all costs associated with the preparation and submission of the bid and WTL will no case be responsible for those costs regardless of the conduct or outcome of the bidding process.

4. BID DOCUMENT

Bidder is expected to examine all instructions, forms, terms and requirement in the bid document. The invitation to bid together with all its attachment thereto shall be considered to be read, understood and accepted by the bidder unless deviations are specifically stated in the seriatim by the bidder. Failure to furnish all information required by the bid document or a bid not substantially responsive to the bid document in every respect may result of the bid.

5. AMENDMENT OF BID DOCUMENT

At any time prior to the deadline for submission of proposals, WTL reserves the right to add/modify/delete any portion of this document by issuance of a Corrigendum, which would be

published on the website and will also be made available to the all the Bidder who have been issued the tender document. The Corrigendum shall be binding on all bidders and will form part of the bid documents.

6. MODIFICATION AND WITHDRAWAL OF BIDS

The bidder cannot modify or withdraw its bid after submission.

7. LANGUAGE OF BID & CORRESPONDENCE

The proposal will be prepared by the Bidder in English language only. All the documents relating to the proposal (including brochures) supplied by the firm should also be in English, and the correspondence between the Bidder & WTL will be in English language only. The correspondence by fax/E-mail must be subsequently confirmed by a duly signed formal copy.

8. BIDDER'S SOLUTION

The bidders are requested to study the Bill of Material supplied with this document carefully. While working out the solution the bidder has to work with the broad minimum specification provided in the tender documents, conforming to the model, make and Part number (wherever provided). While submitting the bid the bidder has to detail out all components needed to complete the system BOM. The bidder is required quote for each item retaining all major components/sub system detailed and specified. As the contractor will be responsible for smooth functioning of the system, availability of spares during the tenure of the warranty period have to be take care by the contractor to maintain the guaranteed uptime.

9. EARNEST MONEY DEPOSIT (EMD) & TENDER FEE

The bidder shall furnish Online Receipt against payment of Tender Fees and Earnest Money Deposit.

10. REFUND OF EMD

EMD will be refunded to the unsuccessful bidders without interest by following guidelines of circular 3975-F(Y) dated 28/07/2016 on final selection of Successful Bidders.

11. FORFEITURE OF EMD

EMD made by Bidder may be forfeited under the following conditions:
If Bidder withdraws the proposal before the expiry of validity period.
During the evaluation process, if a Bidder indulges in any such activity as would jeopardize the process, the decision of WTL regarding forfeiture of EMD shall be final and shall not be called upon question under any circumstances.

If Bidder violates any of the provisions of the terms and conditions of the proposal.

In the case of a successful Bidder, if Bidder fails to:
a) Accept the work order along with the terms and conditions.
b) Furnish performance security.
c) Violates any of the work conditions of this proposal or indulges in any such activities as would jeopardize the work.
d) Submitting false/misleading information/declaration/documents/proof/etc.

The decision of WTL regarding forfeiture of EMD shall be final and shall not be called upon to question under any circumstances, besides, forfeiture of EMD even the Bidder will be deferred from participating in any job for a period of one year.

12. FORMS AND FORMATS

The various inputs for the Techno Commercial as Financial Bids are to be submitted in the format

specified. The bidder shall use the form, wherever specified, to provide relevant information. If form does not provide space for any required information, space at the end of the form or additional sheets shall be used to convey the said information. For all other cases, the bidder shall design a form to hold the required information.

13. LACK OF INFORMATION TO BIDDER

The bidder shall be deemed to have carefully examined the Bid document to his entire satisfaction. Any lack of information shall not relieve the bidder of his responsibility to fulfill his obligation under the bid. If bidder has any queries relating to bid document, then he can send the queries before the Pre Bid Meeting.

14. CONTRACT EXECUTION

On receipt of the Letter of Award the contractor should submit a Performance Bank Guarantee (PBG) equivalent to 10% of the total contract value within three weeks from the date of receipt of Letter of Award/Order. The PBG should be valid for six month more than the warranty period. All delivery of the material will have to be completed within 60 days from the date of acceptance of contract and the contractor has to ensure all activities leading to the commissioning of the contract to be completed within 90 days from the date of award. Subsequent to the award of contract, the contractor will have to arrange for the requisite material as per BOM.

15. TIME SCHEDULE FOR DELIVERY & INSTALLATION

The IP Based CCTV system project for WBP, shall commence on the award of the contract to the implementation partner through a selection process.

Overall Project Implementation Timeline – 180 Days from the date of issue of Work Order.

16. LOCATION FOR DELIVERY & INSTALLATION

As mentioned in Section – B (Scope of Work)

17. LIQUIDATED DAMAGE

Hardware: LD clause:

I. 0.5% of the total Hardware bill value of this segment for every 7 days delay in meeting the delivery schedule
II. The maximum deductible is capped at 5% of the total year wise SLA value.
III. Vendor Termination Clause: -

Termination possibility of MSI in the case of multiple cases of failure to meet SLA terms beyond monthly commitments for 6 continuous months

WTL reserves the right to terminate the contract and WTL will get the job completed by any other competent party. The difference of cost incurred by WTL will be recovered from the contractor and PBG will be invoked.

18. LIABILITY

In case of a default on bidder's part or other liability, WTL shall be entitled to recover damages from the Contractor. In each such instance, regardless of the basis on which WTL is entitled to claim damages from the Contractor (including fundamental breach, negligence, misrepresentation, or other contract or tort claim), Contractor shall be liable for no more than:

- Payment referred to in the Patents and Copyrights clause.
- Liability for bodily injury (including death) or damage to real property and tangible personal property limited to that cause by the Contractor's negligence.
- As to any other actual damage arising in any situation involving nonperformance by Contractor pursuant to or in any way related to the subject of this Agreement, the charge paid by WTL for the individual product or Service that is the subject of the Claim. However, the contractor shall not be liable for

- For any indirect, consequential loss or damage, lost profits, third party loss or damage to property or loss of or damage to data.
- For any direct loss or damage that exceeds the total payment for Contract Price made or expected to be made to the Contractor hereunder.

19. PATENTS & COPYRIGHT

If a third party claims that a product delivered by the Contractor to WTL infringes that party's patent or copyright, the Contractor shall defend WTL against that claim at Contractor's expense and pay all costs, damages, and attorney's fees that a court finally awards or that are included in a settlement approved by the Contractor, provided that WTL.

- Promptly notifies Contractor in writing of the claim
- Allows Contractor to control and co-operate with Contractor in the defense and any related settlement negotiations.

Remedies: If such a claim is made or appears likely to be made, WTL would permit Contractor to enable WTL to continue to use the product, or to modify it, or replace it with one that is at least functionally equivalent. If Contractor determines that none of these alternatives is reasonably available, WTL agrees to return the product to Contractor on Contractor's written request. Contractor will then give WTL a credit equal to for a machine. WTL's net book value (provided WTL has followed generally accepted accounting principles for a generally available software product produced by Contractor (Program) the amount paid by WTL or 12 months charges (whichever is lesser) and for materials the amount paid by WTL for the materials. These will be Contractor's entire obligation regarding any claim of infringement.

20. SUSPENSION OF WORK

WTL shall have the power at any time and from time to time by notice to the Contractor to delay or suspend the progress of the work or any part of the work due to any other adequate reasons and on receipt of such notice the contractor shall forthwith suspend further progress of the work until further notice from WTL. The Contractor shall recommence work immediately after receiving a notice to do so from WTL. The whole or any part of the time lost for such delay or suspension shall, if WTL in its absolute discretion thinks fit, but not otherwise, be added to the time allowed for completion.

21. TERMS OF PAYMENT

Payment terms will be on back-to-back basis, i.e., payment will be made only on receipt of payment from customer. A scheduled payment for the supply, installation and warranty only, shall be made on back to back basis, by WTL, as depicted below:

- 25% Mobilization Advance of total tender value on completion of selection process of Implementation Partner.
- For ANPR & CCTV System --- 60% on completion of delivery of all active and passive equipment to site/district, as per delivery schedule agreed.
- For Body Worn Camera & Night Vision Binocular --- 75% on completion of full delivery of materials including operational training.
- For ANPR & CCTV System --- Balance 15% on completion of installation and commissioning in all sites.

22. GOVERNING LAWS

This contract should be governed by and interpreted by Arbitration clause in accordance with Laws in force in India. The courts at Kolkata shall have exclusive jurisdiction in all matters arising under the contract. The selected vendor shall keep himself fully informed of all current national, state and municipal law and ordinances. The selected vendor shall at their own expense, obtain all necessary permits and license and pay all fees and taxes required by law. These will be selected vendor's entire obligation regarding any claim of infringement. The selected vendor hereto agrees that it shall comply with all applicable union, state and local laws, ordinances, regulations and codes in performing its obligations hereunder, including the procurement of licenses, permits certificates and payment of taxes where required. The selected vendor shall establish and maintain all proper records

(particularly, but without limitation, accounting records) required by any law, code/practice of corporate policy applicable to it from time to time including records and returns as applicable under labor legislation.

23. CORRUPT OR FRAUDULENT PRATICES

The Tender Committee requires that the bidders under this Tender observe the highest standards of ethics during the procurement and execution of such contracts. For this purpose, the definition of corrupt and fraudulent practices will follow the provisions of the relevant laws in force. The Tender Committee will reject a proposal for award if it detects that the bidder has engaged in corrupt or fraudulent practices in competing for the contract in question. The Tender Committee will declare a firm ineligible, either indefinitely or for a stated period of time, if it at any time determines that the firm has engaged in corrupt and fraudulent practices in competing for, or in executing, a contract.

24. BINDING CLAUSE

All decisions taken by the Tender Committee regarding the processing of this tender and award of contract shall be final and binding on all parties concerned. The Tender Committee reserves the right:

- To vary, modify, revise, amend or change any of the terms and conditions mentioned above and,
- To reject any or all the Tender/s without assigning any reason whatsoever thereof or to annul the bidding process and reject all bids at any time prior to award of contract, without thereby incurring any liability to the affected bidder(s) or any obligation to inform the affected bidder(s) of the grounds for such decision.

25. WORKMEN'S COMPENSATION

In every case in which by virtue of the provision of the workmen's compensation Act 1923 or any other relevant acts and rules, compensation to a workman employed by the contractor, is payable, then this should be done by the Contractor. If WTL is obliged to make any compensation under the said rules and acts, then the amount shall be recovered without prejudice, from the bills and due of the Contractor. WTL shall not be bound to contest any claim made against the Contractor in respect of workmen's compensation.

26. CONTRACTOR'S EMPLOYEES

The Contractor shall comply with the provision of all labour legislation including the requirement of the payment of Wage Act 1936 and the rules framed there under and modifications thereof in respect of men employed by him in carrying out the contract. The Contractor must ensure that he complies with PF, ESI regulation for all his deployed employees. The Contractor shall see that all authorized Sub Contractors under him similarly complied with the above requirement.

27. SAFETY MEASURES

The Contractor shall in the course of execution of the work take all necessary precaution for the protection of all persons and property. The Contractor shall take adequate measures to protect the work and present accident during the work. In the event of any accident to any person or persons or damage or injury of any description to any person or property due to failure on the part of the contractor in taking proper precautionary measures the contractor shall be responsible for and must make good the loss the damage at his own cost to the satisfaction of the department and employees of the department shall be indemnified from all claims or liabilities arising there from or any expenses incurred on account thereof.

28. EQUIPMENT

All tools & tackles necessary for the work shall have to be procured by the contractor unless otherwise specified elsewhere in these tender documents. The equipment used by the contractor for a particular work must be appropriate for the type of work. The contractor shall maintain the equipment used on the work properly so that they are in good working condition. In no case shall the contractor use defective or imperfect equipment in the work. The contractor shall arrange to replace or repair all

defective equipment so that the progress of the work is not hampered. No defective equipment should be left at the site of work and the department shall not be responsible for any loss or damage to any of these equipment during the course of the execution of the work.

29. SUB-CONTRACT

The bidder may appoint sub-contractor for execution and maintenance work under their direct supervision and against prior approval of WTL project management team. However, all the responsibilities and liabilities will be lies on the L1 bidder. The Contractor's responsibility is not transferable. No consortium or joint venture partner is allowed.

30. TERMINATION FOR DEFAULT

WTL may without prejudice to any other remedy or right of claim for breach of contract by giving not less than 30 days written notice of default sent to the contractor, terminate the order in whole or in part. If the contractor materially fails to render any or all the services within the time period specified in the contract or any extension thereof granted by WTL in writing and fails to remedy its failure within a period of thirty days after receipt of default notice from WTL. If the project (delivery, commissioning as well as warranty maintenance support is not carried out according to specification due to deficiency in service as per terms of the contract. In such case WTL will invoke the amount held back from the contractor as PBG.

31. BANKRUPTCY

If the contractor becomes bankrupt or have a receiving order made against him or compound with his creditors or being a corporation commence to be wound up, not being a voluntary winding up for the purpose only or amalgamation or reconstruction, or carry on their business under a receiver for the benefit of their creditors or any of them, WTL shall be at liberty to terminate the engagement forthwith without any notice in writing to the contractor or to the liquidator or receiver or to any person in whom the contractor may become vested and without any compensation to give such liquidator or receiver or other person the option of carrying out the engagement subject to their providing a guarantee for the due and faithful performance of the engagement up to an amount to be determined by WTL.

32. FORCE MAJEURE

It is hereby defined as any cause, which is beyond the control of the Contractor or WTL as the case may be, which such party could not foresee or with a reasonable amount of diligence could not have foreseen and which substantially affect the performance of the contract, such as

- War, Hostilities or warlike operations (whether a state of war be declared or not), invasion, act of foreign enemy and civil war.
- Rebellion, revolution, insurrection, mutiny, usurpation of civil or military, government, conspiracy, riot, civil commotion and terrorist area.
- Confiscation, nationalization, mobilization, commandeering or requisition by or under the order of any government or de facto authority or ruler, or any other act or failure to act of any local state or national government authority.
- Strike, sabotage, lockout, embargo, import restriction, port congestion, lack of usual means of public transportation and communication, industrial dispute, shipwreck, shortage of power supply epidemics, quarantine and plague.
- Earthquake, landslide, volcanic activity, fire flood or inundation, tidal wave, typhoon or cyclone, hurricane, nuclear and pressure waves or other natural or physical disaster.

If either party is prevented, hindered or delayed from or in performing any of its obligations under the Contract by an event of Force Majeure, then it shall notify the other in writing of the occurrence of such event and the circumstances of the event of Force Majeure within fourteen days after the occurrence of such event. The party who has given such notice shall be excused from the performance or punctual performance of its obligations under the Contract for so long as the relevant event of Force Majeure continues and to the extent that such party's performance is prevented, hindered or delayed.

The party or parties affected by the event of Force Majeure shall use reasonable efforts to mitigate the effect of the event of Force Majeure upto its or their performance of the Contract and to fulfill its or their obligation under the Contract but without prejudice to either party's right to terminate the Contract.

No delay or nonperformance by either party to this Contract caused by the occurrence of any event of Force Majeure shall.

- Constitute a default or breach of the contract.
- Give rise to any claim fro damages or additional cost or expense occurred by the delay or nonperformance. If, and to the extent, that such delay or nonperformance is caused by the occurrence of an event of Force Majeure.

33. INSURANCE COVERAGE

Appropriate insurance to cover all solution components for the transit period and until the time of its acceptance at the respective site is to be taken by the contractor. As the contractor will carry the risk for the material in his books during transit, the contractor should arrange insurance for the total system as period from the dispatch till Acceptance Test is successfully achieved.

34. WARRANTY & MAINTENANCE

- Contractor will have to provide 3 Years comprehensive warranty on all components for ANPR & CCTV System from the date of go-live of the system and 1 Year Warranty for Body Worn Camera & Night Vision Binocular from the date of supply.
- After completion of comprehensive warranty period WTL may go for fresh AMC with the supplier.
- During the warranty period, no active component should be declared "End of Life". In case it is declared "End of Life" during this period, the vendor has to replace such equipment at their own cost.

35. PERFORMANCE BANK GUARANTEE (PBG)

As a guarantee for timely delivery, installation and commissioning of equipment as well as performance of on-site warranty support, as mentioned in Bill of Material, from the date of final acceptance of systems and pertaining to proper running of the systems, the bidder will have to submit 10% of the contract value as security in the form of Performance Bank Guarantee from any nationalized bank as per format enclosed (Section – N).

36. SI/BIDDER/CONTRACTOR'S RESPONSIBILITIES

Refer Section - A

37. NO WAIVER OF RIGHTS

Neither the inspection by WTL or any of their agents nor any order by WTL for payment of money or any payment for or acceptance of the whole or any part of the works by WTL, nor any extension of time, nor any possession taken by WTL shall operate as a waiver of any provision of the contract or of any power reserved to WTL, or any right to damages here in provided, nor shall any waiver of any breach in the contract be held to be a waiver of any other subsequent breach.

38. ENFORCEMENT OF TERMS

The failure of either party to enforce at any time any of the provision of this contract or any rights in respect thereto or to exercise any option here in provided shall in no way be construed to be a waiver to such provisions, rights or options or in any way to affect the validity of the contract. The exercise by either party of any of its rights herein shall not preclude or prejudice either party from exercising the same or any other right it may have hereunder.

39. PERIOD OF VALIDITY OF OFFER

For the purpose of placing the order, the proposals shall remain valid till 180 days. During the period of validity of proposals, the rates quoted shall not change. In exceptional circumstances, WTL may ask for extension of the period of validity and such a request shall be binding on Bidders. WTL's request and the response to such a request by various Bidders shall be in writing. A Bidder agreeing to such an extension will not be permitted to increase its rates.

40. TAXES & DUTIES

- The prices shall be inclusive of all taxes & levies including GST and other statutory duties as applicable. Rate of taxes should be indicated separately in the Price Bid.
- Contract Price specified in Price Bid should be based on the taxes & duties and charges prevailing at the date one day prior to the last date of Bid submission.
- Statutory deduction, wherever applicable, shall be made from invoice as per government rules. Necessary certificate will be issued for such deductions.
- Bidder submitting a bid shall produce valid statutory documents / certificates with respect to GST, Income Tax, ROC, Prof. Tax, Trade License, etc. All such documents / certificates shall remain valid on the last date of tender submission.
- In case of inter-state transaction, WTL will provide "Waybill". However, statutory charges, if any will be borne by the bidder.
- GST component of the invoice of the bidder may be kept on hold in case there ia any mismatch / irregularity in GST return filling on the part of the bidder.

41. DISCREPANCIES IN BID

- Discrepancy between description in words and figures, the rate which corresponds to the words quoted by the bidder shall be taken as correct.
- Discrepancy in the amount quoted by the bidder due to calculation mistake of the unit rate then the unit rate shall be regarded as firm.
- Discrepancy in totaling or carry forward in the amount quoted by the bidder shall be corrected.

42. BID DUE DATE

The tender shall be submitted not later than the due date and time specified in the Important Dates Sheet. WTL may as its discretion on giving reasonable notice by fax, or any other written communication to all prospective bidders who have been issued the bid documents, extend the bid due date, in which case all rights and obligations of the WTL and the bidders, previously subject to the bid due date, shall thereafter be subject to the new bid due date as extended.

43. LATE BID

Any proposal received after the deadline for submission of proposals may not be accepted.

44. OPENING OF BID BY WTL

Bids shall be opened and downloaded electronically through operation of the process in the e-Tender portal in presence of Tender Committee. Bidders interested to remain present during electronic bid opening may attend the bid opening session at WTL premises at scheduled date & time.

45. CONTACTING WTL

Bidder shall not approach WTL officers beyond office hours and/or outside WTL office premises from the time of the Bid opening to the time of finalization of successful bidder. Any effort by bidder to influence WTL office in the decision on Bid evaluation, Bid comparison or finalization may result in rejection of the Bidder's offer. If the bidder wishes to bring additional information to the notice of WTL, it should be in writing.

46. WTL'S RIGHT TO REJECT ANY OR ALL BIDS

WTL reserves the right to reject any bid and to annul the bidding process and reject all bids at any

time prior to award of Contract, without thereby incurring any liability to the affected bidder(s) or any obligation to inform the affected bidder(s) of the grounds for such decision.

47. BID CURRENCIES

Prices shall be quoted in Indian Rupees, inclusive of all prevailing taxes, levies, duties, cess etc.

48. PRICE

- Price should be quoted in the BOQ format only. No deviation is acceptable.
- Price quoted should be firm, inclusive of packing, forwarding, insurance and freight charges.
- Percentage/specified amount of taxes & duties should be clearly mentioned otherwise WTL reserves the right to reject such vague offer.
- Price to be quoted inclusive of supply, installation & commissioning charges.

49. CANVASSING

Canvassing or support in any form for the acceptance of any tender is strictly prohibited. Any bidder doing so will render him liable to penalties, which may include removal of this name from the register of approved Contractors.

50. NON-TRANSFERABILITY OF TENDER

This tender document is not transferable.

51. FORMATS AND SIGNING OF BID

The original and all copies of the proposals shall be neatly typed and shall be signed by an authorized signatory(ies) on behalf of the Bidder. The authorization shall be provided by written Power of Attorney accompanying the proposal. All pages of the proposal, except for un-amended printed literature, shall be initialed by the person or persons signing the proposal. The proposal shall contain no interlineations, erase or overwriting. In order to correct errors made by the Bidder, all corrections shall be done & initialed with date by the authorized signatory after striking out the original words/figures completely.

52. WITHDRAWAL OF BID

Bid cannot be withdrawn during the interval between their submission and expiry of Bid's validity period. Fresh Bid may be called from eligible bidders for any additional item(s) of work not mentioned herein, if so required.

53. INTERPRETATION OF DOCUMENTS

If any bidder should find discrepancies or omission in the specifications or other tender documents, or if he should be in doubt as to the true meaning of any part thereof, he shall make a written request to the tender inviting authority for correction/clarification or interpretation or can put in a separate sheet along with his technical bid document.

54. SPLITTING OF THE CONTRACT AND CURTAILMENT OF WORK

WTL reserves the right to split up and distribute the work among the successful technically qualified bidders and to curtail any item of work in the schedule partly or fully based on scheme requirement.
As it is a time constrained process, the work may be distributed as mentioned above at L1 rate arrived through the process.

55. PREPARATION OF TENDER

Tender shall be submitted in accordance with the following instructions:

a) Tenders shall be submitted in the prescribed forms. Digital signatures shall be used. Where there is conflict between the words and the figures, the words shall govern.
b) All notations must be in ink or type written. No erasing or overwriting will be permitted. Mistakes may be crossed out and corrections typed or written with ink adjacent thereto and must be initialed in ink by the person or persons signing the tender.
c) Tenders shall not contain any recapitulation of the work to be done. Alternative proposals will not be considered unless called for. No written, oral, telegraphic or telephonic proposals for modifications will be acceptable.
d) Tenders shall be uploaded as notified on or before the date and time set for the opening of tenders in the Notice Inviting Tenders.
e) Tenders subject to any conditions or stipulations imposed by the bidder are liable to be rejected.
f) Each and every page of the tender document must be signed with company seal by the bidder.

56. CLARIFICATION OF BIDS

During evaluation of the bids, the Customer/Tender Committee, at its discretion may ask the bidder for clarification of its bid. The request for the clarification and the response shall be in writing (fax/email) and no change in the substance of the bid shall seek offered or permitted.

57. COMPLIANCE WITH LAW

The contractor hereto agrees that it shall comply with all applicable union, state and local laws, ordinances, regulations and codes in performing its obligations hereunder, including the procurement of licenses, permits certificates and payment of taxes where required.

The contractor shall establish and maintain all proper records (particularly, but without limitation, accounting records) required by any law, code/practice of corporate policy applicable to it from time to time including records and returns as applicable under labor legislation.

58. ERASURES OR ALTERNATIONS

The offers with overwriting and erasures may make the tender liable for rejection if each of such overwriting/erasures/manuscript ions is not only signed by the authorized signatory of the bidder. There should be no hand-written material, corrections or alterations in the offer. Technical details must be completely filled up. Correct technical information of the product being offered must be filled in. Filling up of the information using terms such as "OK", "accepted", "noted", "as given in brochure/manual" is not acceptable. The Customer may treat offers not adhering to these guidelines as unacceptable. The Customer may, at its discretion, waive any minor non-conformity or any minor irregularity in the offer. This shall be binding on all bidders and the Tender Committee reserves the right for such waivers.

59. FINAL INSPECTION

Final inspection may be carried by the authorized representative from WTL & Client.

60. PRE-DISPATCH INSTRUCTION

All materials / equipment's supplied against the purchase order may be subjected to Inspection, check and /or test by the authorized representative from WTL.

61. SITE INSPECTION

Bidder can inspect (at their own cost) the sites if required, for which they have to take necessary permission from WTL in writing. WTL will take at least four days to organize such permission.

62. QUALITY CONTROL

- The contractor is obliged to work closely with WTL act within its authority and abide by directive issued by them on implementation activities.
- The contractor will abide by the safety measures and free WTL from all demands or responsibilities arising from accident/loss of life, the cause of which is due to their negligence. The bidder will pay all indemnities arising from such incidents and will not hold WTL responsible.
- The contractor will treat as confidential all data and information about the system, obtained in the execution of its responsibilities in strict confidence and will not reveal such information to any party without the prior written approval of WTL.
- WTL reserves the right to inspect all phases of contractor's operation to ensure conformity to the specifications. WTL shall have engineers, inspectors or other duly authorized representatives made known to the contractor, present during the progress of the work and such representatives shall have free access to the work at all times. The presence or absence of representatives of WTL does not relieve the contractor of the responsibility for quality control in all phases.
- The Court of Kolkata only will have the jurisdiction to deal with and decide any legal matters or dispute whatsoever arising out of the contract.

63. SERVICE LEVEL AGREEMENT of this Contract

The supplied equipment must be operational seamlessly during 3 years' contract period for ANPR & IP Based CCTV System, otherwise the following SLAs must be adhered to:

1) Calls must be attended within 2 days / 48 hours of logging of complaint / reporting. Complaint should be logged through a dedicated whatsapp group / a dedicated Tech Support Phone Number / a dedicated mail id for this project. So that Call logged details should be summarized later-on as per requirement.

2) Call resolution within 3 days / 72 hours of logging of complaint / reporting. If complaint logged within 10.00 AM, then the same day should be countable as day 1(one) / 1st Day.

The Vendor will not be being libel If there were any electrical failure / Network failure / cut off / Force Majure. These facilities will be provided by client. The concern officer of the site will take care the same.

3) A consolidated report will be published for every quarter for this particular system by the vendor with all details (Call logged date, time, complain attained date & time and resolved date & time). If there will be any issue the same should be shorted out by next 1 week with valid document and justification.

64. GENERAL TERMS

a) All the documents to be submitted by the bidder along with their offer should be duly authenticated by the person signing the offer and if at any point of time during procurement process or subsequently it is detected that documents submitted are forged/tampered/manipulated in any way, the total responsibility lies with the bidder and WTL reserves the full right to take action as may be deemed fit including rejection of the offer and such case is to be kept recorded for any future dealing with them.

b) No Technical/Commercial clarification will be entertained after opening of the tender.

c) Quantity mentioned in the tender document is indicative only and orders shall be placed subject to actual requirement. WTL reserve the right to increase or decrease the quantity specified in the tender.

d) WTL reserve the right to reject or accept or withdraw the tender in full or part as the case may be without assigning the reasons thereof. No dispute of any kind can be raised the right of buyer in any court of law or elsewhere.

e) WTL reserve the right to ask for clarification in the bid documents submitted by the bidder. Documents may be taken if decided by the committee.

f) Supporting technical brochures/catalogues indicating each feature in respect of offered model and make must be submitted along with the offer, in absence of which the offer is liable to be ignored.

g) No dispute by the bidders in regard to Technical/Commercial points will be entertained by WTL and decision taken by the Tender Committee will be final.

h) Discrepancy in the amount quoted by the bidder due to calculation mistake, the unit rate shall be regarded as firm and the totaling or carry in the amount quoted by the bidder shall be corrected accordingly.

i) The price offers shall remain firm within the currency of contract and no escalation of price will be allowed.

j) The acceptance of the tender will rest with the accepting authority who is not bound to accept the lowest or any tender and reserves the right to reject in part or in full any or all tender(s) received and to split up the work among participants without assigning any reason thereof.

k) The customer/WTL at its discretion may extend the deadline for the submission of Bids.

l) The Court of Kolkata only will have the jurisdiction to deal with and decide any legal matters or dispute whatsoever arising out of the contract.

m) Below mentioned clauses are applicable for all Bidders:

Any bidder from a country which shares a land border with India will not eligible to bid in this tender only if the bidder is registered with the Competent Authority [DPIIT OM No.6/18/2019- PPD dated 23.07.2020].

i. ‘‘Bidder’’ (including the term ‘tenderer’, ‘consultant’ or ‘service provider’ in certain contexts) means any person or firm or company, every artificial juridical person not falling in any of the descriptions of bidders stated hereinbefore, including any agency branch or office controlled by such person, participating in a procurement process.
ii. ‘‘Bidder from a country which shares a land border with India’’ for the purpose of above- mentioned Order means:

n) The successful bidder shall not be allowed to sub-contract works to any contractor from a country which shares a land border with India unless such contractor is registered with the Competent Authority.

WEBEL TECHNOLOGY LIMITED

SECTION – F

BID FORM

(Bidders are requested to furnish the Bid Form in the Format given in this section, filling the entire Blank and to be submitted on Letter Head in original)

To
Webel Technology Limited
Plot – 5, Block – BP,
Sector - V,
Salt Lake City,
Kolkata – 700091.

Sub: Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal.

Dear Sir,

1. We the undersigned bidder/(s), having read and examined in details the specifications and other documents of the subject tender no. WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026 , do hereby propose to execute the job as per specification as set forth in your Bid documents.

2. The prices of all items stated in the bid are firm during the entire period of job irrespective of date of completion and not subject to any price adjusted as per in line with the bidding documents. All prices and other terms & conditions of this proposal are valid for a period of 180 (one hundred eighty) days from the date of opening of bid. We further declare that prices stated in our proposal are in accordance with your bidding.

3. We confirm that our bid prices include all other taxes and duties and levies applicable on bought out components, materials, equipment and other items and confirm that any such taxes, duties and levies additionally payable shall be to our account.

4. Earnest Money Deposit & Tender fee: We have transferred EMD & Tender Fee amount online through e-Tender portal.

5. We declare that items shall be executed strictly in accordance with the specifications and documents irrespective of whatever has been stated to the contrary anywhere else in our proposal. Further, we agree that additional conditions, deviations, if any, found in the proposal documents other than those stated in our deviation schedule, save that pertaining to any rebates offered shall not be given effect to.

6. If this proposal is accepted by you, we agree to provide services and complete the entire work, in accordance with schedule indicated in the proposal. We fully understand that the work completion schedule stipulated in the proposal is the essence of the job, if awarded.

7. We further agree that if our proposal is accepted, we shall provide a Performance Bank Guarantee of the value equivalent to ten percent (10%) of the Order value as stipulated in Financial Bid (BOQ).

8. We agree that WTL reserves the right to accept in full/part or reject any or all the bids received or split order within successful bidders without any explanation to bidders and his decision on the subject will be final and binding on Bidder.

Dated, this ……..day of ……2026

Thanking you, we remain,

Yours faithfully

……
Signature

……..
Name in full

……..
Designation

Signature & Authorized Verified by

……
Signature

……
Name in full

……
Designation

……
Company Stamp

WEBEL TECHNOLOGY LIMITED

SECTION – G

TECHNO COMMERCIAL EVALUATION & AWARDING OF CONTRACT

1. EVALUATION PROCEDURE

- The Eligibility Criteria (Section - D) will be evaluated by Tender Committee and those qualify will be considered for further evaluation.
- The Tender Committee shall verify the Technical Specification (Technical Specification & Compliance Statement, Section – Q) Deviation in specification shall not be allowed. Bidder qualified in Technical Specification shall be considered for further evaluation.
- The Tender Committee would evaluate the Techno Commercial Evaluation.
- Bidders after qualifying in Techno Commercial Evaluation will only be considers for Financial Bid Evaluation.

2. EVALUATION CRITERIA

Techno Commercial Evaluation

The evaluation methodology would take into consideration both the Techno Commercial responsiveness as well as the financial response. During the evaluation process, the evaluation committee will assign each desirable/preferred feature against the Techno Commercial Bid.

3. FINAL EVALUATION

Financial Proposal of the bidders qualifying in the evaluation of Techno Commercial will be evaluated. The bidder who has qualified in the Techno Commercial and returns with lowest quote (L1) in Financial Bid will normally be awarded the contract subject to Post Qualification.

4. AWARDING OF CONTRACT

An affirmative Post Qualification determination will be prerequisite for award of the contract to the most overall responsive bidder for this project. Bidders, if disqualified in the technical evaluation, it will result in rejection of bidder's bid. Technically qualified bidders shall be evaluated for price bid. The lowest bidder shall be determined through price bid evaluation. WTL will award the contract to the successful bidder whose bid has been determined to be substantially responsive after final negotiation may held with the most responsive bidder (L1), if required.

- Bidders must submit price bid for this project. Any non-compliance to the price bid shall lead to rejection.
- L1 Bidders shall be awarded the contract for this project.

5. POST QUALIFICATION

The determination will evaluate the Bidder's financial, technical, design, integration, customization, production, management and support capabilities and will be based on an examination of the documentary evidence of the Bidder's qualification, as well as other information WTL deems necessary and appropriate. This determination may include visits or interviews with the Bidder's client's reference in its bid, site inspection, and any other measures. At the time of post-qualification, Department of Par & e-Governance may also carry out tests to determine that the performance or functionality of the Information System offered meets those stated in the detailed Technical Specification.

WEBEL TECHNOLOGY LIMITED

SECTION – H

GUIDANCE FOR E-TENDERING

Instructions / Guidelines for electronic submission of the tenders have been annexed for assisting the Bidders to participate in e-Tendering.

1. **Registration of Bidder:**
   Any Bidder willing to take part in the process of e-Tendering will have to be enrolled & registered with the Government e-Procurement System through logging on to **https://wbtenders.gov.in.** The Bidder is to click on the link for e-Tendering site as given on the web portal.

2. **Digital Signature Certificate (DSC):**
   Each Bidder is required to obtain a Class-II or Class-III Digital Signature Certificate (DSC) for submission of tenders from the approved service provider of the National Informatics Centre (NIC) on payment of requisite
   amount. Details are available at the Web Site stated above. DSC is given
   as a USB e-Token.

3. The Bidder can search & download N.I.T. & BOQ electronically from computer once he logs on to the website mentioned above using the Digital Signature Certificate. This is the only mode of collection of Tender Documents.

4. **Participation in more than one work:**
   A prospective bidder shall be allowed to participate in the job either in the capacity of individual or as a partner of a firm. If, found to be applied severally in a single job all the applications will be rejected.

5. **Submission of Tenders:**
   Tenders are to be submitted through online to the website stated above in two folders at a time, one in Techno Commercial Proposal & the other is Financial Proposal before the prescribed date & time using the Digital Signature Certificate (DSC). The documents are to be uploaded virus scanned copy duly Digitally Signed. The documents will get encrypted (transformed into non readable formats)

The proposal should contain scanned copies of the following in two covers (folders).

Techno Commercial Cover:

Technical Document1

1. Bid Form as per format (Section – F)
2. Other documents, if any

Technical Document2

1. N I T Declaration duly stamped & signed in bidder's letter head, (Section – P)
2. Other documents, if any

Technical Compliance

1. Detailed Technical Specification with required documents, Section – R
2. Manufacturer Authorization Form, Section – S
3. Detailed Make, Mode with required documents, Section – Q

Financial Cover:

BOQ (Bill of Quantity) will be downloaded and same will be uploaded with quoted rates. While uploading BOQ file name shall remain unchanged. Absence of this document shall lead to summary rejection of the bid.

WEBEL TECHNOLOGY LIMITED

NON-STATUTARY COVER (MY SPACE) CONTAIN FOLLOWING DOCUMENT:
(In each folder, scanned coy will be uploaded with single file having multiple pages)

Sl. No.	Category Name	Sub Category Name	Sub Category Description
A	CERTIFICATES	A1. CERTIFICATES	• GST Registration Number • PAN • Document as per Section – D
B	COMPANY DETAILS	B1. COMPANY DETAILS 1	• Document as per Section – D • Declaration as per Section – B
		B2. COMPANY DETAILS 2	• ISO Certificate as per Section –D
C	CREDENTIAL	CREDENTIAL 1	• Order copies as per Section – D
		CREDENTIAL 2	• Product brochure • Other documents, if any
D	DECLARATION	DECLARATION 1	• List of Clients as per format (Section – N) • Financial Capability of Bidder as per format (Section – K)
		DECLARATION 2	• Document as per Section – D • Other documents, if any
		DECLARATION 3	• Bidder's Details as per format (Section – L) • Service Centre Details as per format (Section – R)
		DECLARATION 4	• Details of Capability as per format (Section – J) • Checklist as per Section – T
		DECLARATION 5	• Other documents, if any
F	FINANCIAL INFO	P/L & BALANCE SHEET 2022-2023	P/L & BALANCE SHEET 2022-2023
		P/L & BALANCE SHEET 2023-2024	P/L & BALANCE SHEET 2023-2024
		P/L & BALANCE SHEET 2024-2025	P/L & BALANCE SHEET 2024-2025

WEBEL TECHNOLOGY LIMITED

SECTION – I

TOTAL UN-PRICE BILL OF MATERIAL

(As per Technical Specification as mentioned in SECTION – R)

Sr.No	Item Description	UoM	Qty
	SURVEILLANCE CAMERA		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**617**
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**617**
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**32**
	ANPR CAMERA		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**128**
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**128**
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**115**
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**114**
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**2**
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**114**
10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**13**
11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**49**
12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**52**
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**116**
14	1 KVA Offline UPS with Battery	**PCS**	**114**
15	17" LED Display for each location	**PCS**	**114**
16	2 Meter Length HDMI Cable	**PCS**	**114**
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**41090**
18	RJ-45 Connector	**PCS**	**1490**
19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**228**
20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**41090**
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**114**
22	Power Board with MCB	**PCS**	**114**
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Alipurduar Police District	**Each Site**	**8**
24	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Coochbehar Police District	**Each Site**	**17**

25	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Dakshin Dinajpur Police District	**Each Site**	**9**
26	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Darjeeling Police District	**Each Site**	**15**
27	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Islampur Police District	**Each Site**	**12**
28	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Raigang Police District	**Each Site**	**13**
29	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Jalpaiguri Police District	**Each Site**	**8**
30	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Kalimpong Police District	**Each Site**	**9**
31	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Malda Police District	**Each Site**	**19**
32	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Siliguri Commissionerate	**Each Site**	**4**
33	Supply of Body Worn Camera (with 1 Year Warranty)	**PCS**	**493**
34	Supply of Night Vision Binocular (with 1 Year Warranty)	**PCS**	**44**

WEBEL TECHNOLOGY LIMITED

DISTRICT & COMMISSIONRATE WISE BOQ OF THE PROJECT

SL. NO	DESCRIPTION	UNIT	QTY.
	ALIPURDUAR POLICE DISTRICT		
1.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**24**
1.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**24**
1.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**1**
1.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**16**
1.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**16**
1.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**15**
1.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**8**
1.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
1.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**8**
1.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**1**
1.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**7**
1.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
1.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**8**
1.14	1 KVA Offline UPS with Battery	**PCS**	**8**
1.15	17" LED Display for each location	**PCS**	**8**
1.16	2 Meter Length HDMI Cable	**PCS**	**8**
1.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**2480**
1.18	RJ-45 Connector	**PCS**	**80**
1.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**16**
1.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**2480**
1.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**8**
1.22	Power Board with MCB	**PCS**	**8**
1.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Alipurduar Police District	**Each Site**	**8**
	COOCHBEHAR POLICE DISTRICT		
2.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**90**
2.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**90**
2.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**5**
2.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**20**
2.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**20**
2.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**19**
2.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**17**

2.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
2.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**17**
2.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**1**
2.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**9**
2.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**7**
2.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**17**
2.14	1 KVA Offline UPS with Battery	**PCS**	**17**
2.15	17" LED Display for each location	**PCS**	**17**
2.16	2 Meter Length HDMI Cable	**PCS**	**17**
2.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**6100**
2.18	RJ-45 Connector	**PCS**	**220**
2.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**34**
2.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**6100**
2.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**17**
2.22	Power Board with MCB	**PCS**	**17**
2.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Coochbehar Police District	**Each Site**	**17**
	DAKSHIN DINAJPUR POLICE DISTRICT		
3.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**42**
3.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**42**
3.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**5**
3.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**14**
3.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**14**
3.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**14**
3.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**9**
3.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
3.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**9**
3.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
3.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**7**
3.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
3.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**9**
3.14	1 KVA Offline UPS with Battery	**PCS**	**9**
3.15	17" LED Display for each location	**PCS**	**9**
3.16	2 Meter Length HDMI Cable	**PCS**	**9**
3.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**3220**
3.18	RJ-45 Connector	**PCS**	**112**
3.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**18**
3.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**3220**
3.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**9**
3.22	Power Board with MCB	**PCS**	**9**

3.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Dakshin Dinajpur Police District	**Each Site**	**9**
	DARJEELING POLICE DISTRICT		
4.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**90**
4.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**90**
4.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**6**
4.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**16**
4.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**16**
4.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**15**
4.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**15**
4.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**1**
4.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**15**
4.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**1**
4.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**6**
4.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**8**
4.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**16**
4.14	1 KVA Offline UPS with Battery	**PCS**	**15**
4.15	17" LED Display for each location	**PCS**	**15**
4.16	2 Meter Length HDMI Cable	**PCS**	**15**
4.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**5680**
4.18	RJ-45 Connector	**PCS**	**208**
4.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**30**
4.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**5680**
4.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**15**
4.22	Power Board with MCB	**PCS**	**15**
4.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Darjeeling Police District	**Each Site**	**15**
	ISLAMPUR POLICE DISTRICT		
5.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**80**
5.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**80**
5.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**4**
5.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**8**
5.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**8**
5.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**8**
5.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**12**
5.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
5.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**12**
5.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
5.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**4**

5.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**8**
5.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**12**
5.14	1 KVA Offline UPS with Battery	**PCS**	**12**
5.15	17" LED Display for each location	**PCS**	**12**
5.16	2 Meter Length HDMI Cable	**PCS**	**12**
5.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**4640**
5.18	RJ-45 Connector	**PCS**	**176**
5.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**24**
5.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**4640**
5.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**12**
5.22	Power Board with MCB	**PCS**	**12**
5.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Islampur Police District	**Each Site**	**12**
	RAIGANJ POLICE DISTRICT		
6.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**80**
6.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**80**
6.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**0**
6.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**10**
6.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**10**
6.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**8**
6.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**13**
6.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**1**
6.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**13**
6.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
6.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
6.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**9**
6.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**14**
6.14	1 KVA Offline UPS with Battery	**PCS**	**13**
6.15	17" LED Display for each location	**PCS**	**13**
6.16	2 Meter Length HDMI Cable	**PCS**	**13**
6.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**4800**
6.18	RJ-45 Connector	**PCS**	**180**
6.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**26**
6.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**4800**
6.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**13**
6.22	Power Board with MCB	**PCS**	**13**
6.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Raigang Police District	**Each Site**	**13**
	JALPAIGURI POLICE DISTRICT		
7.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**48**
7.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**48**

7.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**4**
7.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**8**
7.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**8**
7.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**8**
7.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**8**
7.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
7.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**8**
7.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
7.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**4**
7.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**4**
7.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**8**
7.14	1 KVA Offline UPS with Battery	**PCS**	**8**
7.15	17" LED Display for each location	**PCS**	**8**
7.16	2 Meter Length HDMI Cable	**PCS**	**8**
7.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**3040**
7.18	RJ-45 Connector	**PCS**	**112**
7.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**16**
7.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**3040**
7.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**8**
7.22	Power Board with MCB	**PCS**	**8**
7.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Jalpaiguri Police District	**Each Site**	**8**
	KALIMPONG POLICE DISTRICT		
8.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**50**
8.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**50**
8.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**0**
8.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**8**
8.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**8**
8.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**6**
8.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**9**
8.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
8.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**9**
8.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
8.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
8.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**5**
8.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**9**
8.14	1 KVA Offline UPS with Battery	**PCS**	**9**
8.15	17" LED Display for each location	**PCS**	**9**
8.16	2 Meter Length HDMI Cable	**PCS**	**9**

8.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**3140**
8.18	RJ-45 Connector	**PCS**	**116**
8.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**18**
8.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**3140**
8.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**9**
8.22	Power Board with MCB	**PCS**	**9**
8.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Kalimpong Police District	**Each Site**	**9**
	MALDA POLICE DISTRICT		
9.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**107**
9.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**107**
9.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**7**
9.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**20**
9.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**20**
9.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**18**
9.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**19**
9.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
9.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**19**
9.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**2**
9.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**8**
9.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**9**
9.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**19**
9.14	1 KVA Offline UPS with Battery	**PCS**	**19**
9.15	17" LED Display for each location	**PCS**	**19**
9.16	2 Meter Length HDMI Cable	**PCS**	**19**
9.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**6950**
9.18	RJ-45 Connector	**PCS**	**254**
9.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**38**
9.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**6950**
9.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**19**
9.22	Power Board with MCB	**PCS**	**19**
9.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Malda Police District	**Each Site**	**19**
	SILIGURI COMMISSIONRATE		
10.01	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	**PCS**	**8**
10.02	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	**PCS**	**8**
10.03	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**0**
10.04	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	**PCS**	**8**
10.05	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	**PCS**	**8**
10.06	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	**PCS**	**4**

10.07	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	**PCS**	**4**
10.08	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	**PCS**	**0**
10.09	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	**PCS**	**4**
10.10	4 TB SATA Internal Surveillance Hard Disk	**PCS**	**4**
10.11	6 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
10.12	8 TB SATA Internal Surveillance Hard Disk	**PCS**	**0**
10.13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	**PCS**	**4**
10.14	1 KVA Offline UPS with Battery	**PCS**	**4**
10.15	17" LED Display for each location	**PCS**	**4**
10.16	2 Meter Length HDMI Cable	**PCS**	**4**
10.17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	**MTR**	**1040**
10.18	RJ-45 Connector	**PCS**	**32**
10.19	UTP CAT-6 Patch Cord 1 Meters	**PCS**	**8**
10.20	Overhead cable Catenary work with GI Wire for outdoor wiring	**MTR**	**1040**
10.21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	**Lot**	**4**
10.22	Power Board with MCB	**PCS**	**4**
10.23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty for above BOQ of Siliguri Commissionerate	**Each Site**	**4**

OPTION WISE BOQ FOR ALL LOCATIONS

OPTION :- 1

2 No. ANPR Camera + 2 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	2
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	2
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	2
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	2
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	1
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	1
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	260
18	RJ-45 Connector	PCS	8
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	260
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 2

2 No. ANPR Camera + 3 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	3
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	3
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	2
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	2
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	2
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	1
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	310
18	RJ-45 Connector	PCS	10
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	310
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 3

2 No. ANPR Camera + 4 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	4
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	4
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	1
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	2
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	2
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	2
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	1
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	360
18	RJ-45 Connector	PCS	12
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	360
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 4

3 No. ANPR Camera + 2 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	2
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	2
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	1
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	3
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	3
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	3
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	1
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	340
18	RJ-45 Connector	PCS	10
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	340
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 5

3 No. ANPR Camera

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	3
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	3
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	2
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	1
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	240
18	RJ-45 Connector	PCS	6
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	240
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 6

4 No. ANPR Camera

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	0
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	4
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	4
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	3
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	1
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	1
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	2
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	320
18	RJ-45 Connector	PCS	8
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	320
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 7

5 No. ANPR Camera

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	0
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	5
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	5
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	5
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	1
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	1
12	8 TB SATA Internal Surveillance Hard Disk	PCS	
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	2
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	450
18	RJ-45 Connector	PCS	10
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	450
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 8

6 No. ANPR Camera

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	6
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	6
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	6
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	1
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	1
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	2
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	540
18	RJ-45 Connector	PCS	12
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	540
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 9

4 No. ANPR Camera + 4 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	4
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	4
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	2
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	4
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	4
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	2
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	1
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	1
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	2
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	560
18	RJ-45 Connector	PCS	16
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	560
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

OPTION :- 10

8 Nos. Bullet Cameras

SL. NO	DESCRIPTION	UNIT	QTY.
	SURVEILLANCE CAMERA SYSTEM		
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	8
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	8
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	ANPR SYSTEM		
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	0
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	
	Common Item for Both System		
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	1
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	1
10	4 TB SATA Internal Surveillance Hard Disk	PCS	
11	6 TB SATA Internal Surveillance Hard Disk	PCS	
12	8 TB SATA Internal Surveillance Hard Disk	PCS	1
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	1
14	1 KVA Offline UPS with Battery	PCS	1
15	17" LED Display for each location	PCS	1
16	2 Meter Length HDMI Cable	PCS	1
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	400
18	RJ-45 Connector	PCS	16
19	UTP CAT-6 Patch Cord 1 Meters	PCS	2
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	400
21	3 Core 1.5 sq MM Non Armoured Power Cable with Laying	Lot	1
22	Power Board with MCB	PCS	1
23	Supply, Installation, Testing, Commissioning & Project Management Cost including 3 Years Comprehensive Warranty	Each Site	1

Summary of Multiple Options and District Wise Allocations

Sl No	Police District & Commissionrate	Option:-1	Option:-2	Option:-3	Option:-4	Option:-5	Option:-6	Option:-7	Option:-8	Option:-9	Option:-10
1	ALIPURDWAR PD	4	4	1							
2	COOCHBEHAR PD	5	4	3							7
3	DAKSHIN DINAJPUR PD		2	5							2
4	DARJEELING PD			6			1				8
5	ISLAMPUR PD			4							8
6	RAIGANJ PD	1	2				1				9
7	JALPAIGURI PD			4							4
8	KALIMPONG PD	2	2								5
9	MALDA PD		1	8			1				10
10	SILIGURI COMMISSIONRATE										
		12	15	31	0	0	3	0	0	0	53

WEBEL TECHNOLOGY LIMITED

SECTION – J

DETAILS OF TECHNICAL CAPABILITY OF BIDDER

Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026

Sl. No.	Project Name	Start Date	End Date / Status	Brief description of project & scope of work (Implementation, operation & maintenance)	Type of project	Approx value of the project	Contact details of the Customer

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Stamp of the Company: _____

a. Type of Project shall indicate the implementation of services (Networking Setup, System Integration).
b. Scope of work shall indicate whether it is implementation, Operation or maintenance.
c. Submit Customer Order Copy details of the order indicating the project value, customer contact details, project completion certificate, customer satisfaction certificate etc.

WEBEL TECHNOLOGY LIMITED

SECTION – K

FINANCIAL CAPABILITY OF BIDDER

(Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026)

FINANCIAL INFORMATION

Sl. No.	Name of the Bidder	Turnover (Rs. / Crores)		
		2024-2025	2023-2024	2022-2023
1				

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Stamp of the Company: _____

WEBEL TECHNOLOGY LIMITED

SECTION – L

BIDDERS'S DETAILS

Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026

1	Name of the Firm	
2	Registered Office Address	
	Contact Number	
	Fax Number	
	E-mail	
3	Correspondence / Contact address	
	Name & Designation of Contact person	
	Address	
	Contact Number	
	Fax Number	
	E-mail	
4	Is the firm a registered company? If yes, submit documentary proof	
	Year and Place of the establishment of the company	
6	Former name of the company, if any	
7	Is the firm ▪ a Government/ Public Sector Undertaking ▪ a propriety firms ▪ a partnership firm (if yes, give partnership deed) ▪ a limited company or limited corporation ▪ a member of a group of companies, (if yes, give ▪ name and address and description of other companies) ▪ a subsidiary of a large corporation (if yes give the name and address of the parent organization). If the company is subsidiary, state what involvement if any, will the parent company have in the project.	
8	Is the firm registered with Sales Tax department? If yes, submit valid GST Registration certificate.	
9	Is the firm registered for Service Tax with Central Excise Department (Service Tax Cell)? If yes, submit valid Service Tax registration certificate.	
10	Total number of employees. Attach the organizational chart showing the structure of the organization.	
11	Are you registered with any Government/ Department/ Public Sector Undertaking (if yes, give details)	
12	How many years has your organization been in business under your present name? What were your fields when you established your organization	
13	What type best describes your firm? (Purchaser reserves the right to verify the claims if necessary) ▪ Manufacturer ▪ Supplier ▪ System Integrator ▪ Consultant ▪ Service Provider (Pl. specify details) ▪ Software Development ▪ Total Solution provider (Design, Supply, Integration, O&M) ▪ IT Company	

14	Number of Offices in district headquarters in West Bengal	
15	Is your organization having ISO 9001:2015 certificates?	
16	List the major clients with whom your organization has been / is currently associated.	
17	Have you in any capacity not completed any work awarded to you? (If so, give the name of project and reason for not completing the work)	
18	Have you ever been denied tendering facilities by any Government / Department / Public sector Undertaking? (Give details)	

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Company Rubber Stamp: _____

WEBEL TECHNOLOGY LIMITED

SECTION – M

PRE-BID MEETING QUERY

Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026

Name of the Bidder:

Queries

Sl. No.	Section No.	Clause No.	Page No.	Queries

Note: The filled form to be submitted in XLS and PDF Format. There is a cut off date for receiving of queries before Pre Bid Meeting. Queries received after the cutoff period will not be accepted. The Purchaser reserves the right to respond all queries over e-mail.

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Company Rubber Stamp: _____

WEBEL TECHNOLOGY LIMITED

SECTION - N

LIST OF CLIENTS OF SIMILAR ORDERS

(Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026)

Sl. No.	Name of the Client	Address	Contact Person	Designation	Contact Numbers

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Company Rubber Stamp: _____

WEBEL TECHNOLOGY LIMITED

SECTION – O

PROFORMA FOR PERFORMANCE BANK GUARANTEE

(On non-judicial stamp paper of appropriate value to be purchased in the name of executing Bank)

PROFORMA OF BANK GUARANTEE FOR SECURITY DEPOSIT –CUM-PRFORMANCE GUARANTEE

Ref …….. Bank Guarantee no…….

Date……..

PROFORMA OF BG FOR SECURITY DEPOSIT

KNOW ALL MEN BY THESE PRESENTS that in consideration of WEBEL TECHNOLOGY LIMTED, a Government of West Bengal Undertaking incorporated under the Companies Act, 1956 having its Registered office at Plot - 5, Block BP, Sector V, Kolkata-700 091 (hereinafter called ''The Purchaser'') having agreed to accept from _____(hereinafter called ''The Contractor'') Having its Head Office at _____, a Bank guarantee for Rs. _____ in lieu of Cash Security Deposit for the due fulfillment by the Contractor of the terms & conditions of the Work Order No. _____dated_____ issued by the Purchaser for _____ (hereinafter called ''the said work order _____ _____dated_____)''. We _____ (Name & detailed address of the branch) (hereinafter called ''the Guarantor'') do hereby undertake to indemnify and keep indemnified the Purchaser to the extent of Rs._____ (Rupees _____ _____) only against any loss or damage caused to or suffered by the Purchaser by reason of any breach by the Contractor of any of the terms and conditions contained in the said Work Order No. _____ dated_____ of which breach the opinion of the Purchaser shall be final and conclusive.

(2) AND WE, _____DO HEREBY Guarantee and undertake to pay forthwith on demand to the Purchaser such sum not exceeding the said sum of _____Rupees_____) only as may be specified in such demand, in the event of the Contractor failing or neglecting to execute fully efficiently and satisfactorily the order for _____ _____ Work Order no. , _____dated _____

(3) WE _____ further agree that the guarantee herein contained shall remain in full force and effect during the period that would be taken for the performance of the said order as laid down in the said Work Order No. _____ dated _____ including the warranty obligations and that it shall continue to be enforceable till all the dues of the Purchaser under or by virtue of the said Work Order No. _____ dated _____ have been fully paid and its claims satisfied or is charged or till the Purchaser or its authorized representative certified that the terms and conditions of the said Work Order No. _____ dated _____ have been fully and properly carried out by the said contractor and accordingly discharged the guarantee.

(4) We _____ the Guarantor undertake to extend the validity of Bank Guarantee at the request of the contractor for further period of periods from time to time beyond its present validity period failing which we shall pay the Purchaser the amount of Guarantee.

(5) The liability under the Guarantee is restricted to Rs. _____ (Rupees _____ _____) only and will expire on _____ and unless a claim in writing is presented to us or an action or suit to enforce the claim is filled against us within 6 months from _____ all your rights will be forfeited and we shall be relieved of and discharged from all our liabilities (thereinafter)

(6) The Guarantee herein contained shall not be determined or affected by liquidation or winding up or insolvency or closer of the Contractor.

(7) The executants has the power to issue this guarantee on behalf of Guarantor and holds full and valid power of Attorney granted in his favour by the Guarantor authorizing him to execute the Guarantee.

(8) Notwithstanding anything contained herein above, our liability under this guarantee is restricted to Rs. _____ (Rupees _____) only and our guarantee shall remain in force up to _____ and unless a demand or claim under the guarantee is made on us in writing on or before _____ all your rights under the guarantee shall be forfeited and we shall be relieved and discharged from all liabilities there under.

WE, _____ lastly undertake not to revoke this guarantee during the currency except with the previous consent of the Purchaser in writing. In witness whereof we _____have set and subscribed our hand on this _____ day of _____.

SIGNED, SEALED AND DELIVERED

_____
(Stamp of the executants)

WITNESS

1) _____

2) _____
(Name & address in full with Rubber Stamp)

WEBEL TECHNOLOGY LIMITED

INSTRUCTIONS FOR FURNISHING BANK GUARANTEE

1. Bank Guarantee (B.G.) for Advance payment, Mobilization Advance, B.G. for security Deposit-cum-Performance Guarantee, Earnest Money should be executed on the Non- Judicial Stamp paper of the applicable value and to be purchased in the name of the Bank.
2. The Executor (Bank authorities) may mention the Power of Attorney No. and date of execution in his/her favour with authorization to sign the documents. The Power of Attorney is to be witnessed by two persons mentioning their full name and address.
3. The B.G. should be executed by a Nationalised Bank/ Scheduled Commercial Bank preferably on a branch located in Kolkata. B.G. from Co-operative Bank / Rural Banks is not acceptable.
4. A Confirmation Letter of the concerned Bank must be furnished as a proof of genuineness of the Guarantee issued by them.
5. Any B.G. if executed on Non-Judicial Stamp paper after 6 (six) months of the purchase of such stamp shall be treated as non-valid.
6. Each page of the B.G. must bear signature and seal of the Bank and B.G. Number.
7. The content of the B.G. shall be strictly as Proforma prescribed by WTL in line with Purchase Order /LOI/ Work Order etc. and must contain all factual details.
8. Any correction, deletion etc. in the B.G. should be authenticated by the Bank Officials signing the B.G.
9. In case of extension of a Contract the validity of the B.G. must be extended accordingly.
10. B.G. must be furnished within the stipulated period as mentioned in Purchase Order / LOI / Work Order etc.
11. Issuing Bank / The Bidder are requested to mention the Purchase Order / Contract / Work Order reference along with the B.G. No. For making any future queries to WTL.

WEBEL TECHNOLOGY LIMITED

SECTION – P

NIT DECLARATION FOR BIDDER

(Bidders are requested to furnish the Format given in this section, filling the entire Blank and to be submitted on Bidder's Letter Head)

To
Webel Technology Limited
Plot–5, Block–BP, Sector-V,
Salt Lake City,
Kolkata–700091.

Sub: Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal

Dear Sir,

We the undersigned bidder/(s) declare that we have read and examined in details the specifications and other documents of the subject Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026 for Supply, Installation, Testing, Commissioning of ANPR & IP Based CCTV Surveillance system of 09 Police District & 01 Commissionerate and Supply of Body Worn Camera & Night Vision Binocular under Inspector General of Police (North Bengal Region), West Bengal in e-Tender website.

We further declare that we have agreed and accepted all the clauses / sub-clauses / formats / terms & conditions other requirements related to the said tender and we will abide by the same as mentioned in the tender document while participating and executing the said tender.

Thanking you, we remain

Yours faithfully

……
Signature

……..
Name in full

……..
Designation

……..
Company Stamp

Dated, this……..day of……2026

WEBEL TECHNOLOGY LIMITED

SECTION – Q

MAKE & MODEL / PART NUMBER DECLARATION

(Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026)

Sl.	Item	Qty	Unit	Make	Model / Part No
	SURVEILLANCE CAMERA SYSTEM				
1	4 Megapixel IR PoE Motorized Zoom Lens Bullet Network Camera with WDR	PCS	617		
2	Clamp for Camera Fixing with Outdoor PVC Junction Box for Bullet Camera	PCS	617		
3	6 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	32		
	ANPR SYSTEM				
4	4 Megapixel WDR two Lane ANPR Camera with Varifocal Lens and IR Outdoor Housing	PCS	128		
5	Clamp for Camera Fixing with Outdoor PVC Junction Box for ANPR Camera	PCS	128		
6	7 Meter Height GI / MS Pole with Base Plate & Top Cover including RCC foundation with Installation	PCS	115		
	Common Item for Both System				
7	12U Pole Mount Outdoor Rack with Fan, PDU, Tray & other required accessories.	PCS	114		
8	4U Pole Mount Outdoor Rack with Fan, PDU & other required accessories.	PCS	2		
9	8 Channel 4K & H.265, 2 SATA, Network Video Recorder	PCS	114		
10	4 TB SATA Internal Surveillance Hard Disk	PCS	13		
11	6 TB SATA Internal Surveillance Hard Disk	PCS	49		
12	8 TB SATA Internal Surveillance Hard Disk	PCS	52		
13	PoE Switch - 8 Port Gigabit PoE ports + 2 Gigabit Uplink Ports	PCS	116		
14	1 KVA Offline UPS with Battery	PCS	114		
15	17" LED Display for each location	PCS	114		
16	2 Meter Length HDMI Cable	PCS	114		
17	UTP Outdoor Double Jacket CAT-6 Cable with Laying	MTR	41090		
18	RJ-45 Connector	PCS	1490		
19	UTP CAT-6 Patch Cord 1 Meters	PCS	228		
20	Overhead cable Catenary work with GI Wire for outdoor wiring	MTR	41090		
21	3 Core 1.5 sq. MM Non Armoured Power Cable with Laying	Lot	114		
22	Power Board with MCB	PCS	114		
23	Body Worn Camera	PCS	493		
24	Night Vision Binocular	PCS	44		

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Company Rubber Stamp: _____

WEBEL TECHNOLOGY LIMITED

SECTION – R

TECHNICAL SPECIFICATION COMPLIANCE STATEMENT

(Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026)

Eligibility Criteria for IP CCTV Camera, ANPR Camera & Network Video Recorder OEM:

Eligibility Criteria	Compliance with Document
CCTV OEM company should not be technically rejected in any Govt. tender in WB for their origin from any land border sharing countries of India.	
OEM should have Service Centers in WB in their own name. This is to be supported with documentary evidence.	
The CCTV OEM should have CMMI Level 5 or above or equivalent certification.	
The CCTV OEM should have below ISO Certifications for Quality,	
Management system for manufacturing of all types of Cameras & NVR / DVR/Storage. All the CCTV Components (Camera, VMS, NVR, DVR, etc.) should be from same OEM for seamless integration and ease of operation. The Bidder/s shall attach the copy of the OEM's ISO Certificate along with the bid. > ISO 9001:2015 > ISO 14001:2015 > ISO 27001:2013 > ISO 45001:2018 Non Malicious Code Undertaking Letter By OEM The OEM should have cloud for plug & play remote viewing; the Cloud must be hosted in INDIA for protection of public privacy and related data from security threats.	
Certificate of Non-Obsolescence: OEM must provide a certificate that the proposed model of CCTV products must not become obsolete /End of Life (EOL) within a period of 5 years, in case it gets EOL due to technology advancement then OEM will support with equivalent or higher model.	
All the proposed cameras should be Make in India and STQC Certified.	
CCTV OEM company for Camera/Storage should have its own company registered in India (under Incorporation of Companies Act, 1956/ 2013) for 15 years or more. Any representation through a Dealer/ Distributor/ Joint Venture/ consortium/ subsidiary shall not be treated as OEM. This has to be supported by necessary statutory documents	
Original Equipment Manufacturer (OEM) of Camera & Storage, should have Average Annual Financial Turnover not less than Rs. 500 Crores. (in India only for CCTV works) for the last Five years ending March 2026	

4MP IR Bullet Camera with Motorized Varifocal lens				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Image Sensor	1/2.7" Progressive Scan CMOS or better		
2	Min. Illumination	Color: 0.001 lux, B/ W :.0.0001 lux, 0 lux with IR		
3	Shutter Speed	1/3 s to 1/100,000 s or better		
4	Day & Night	IR Cut Filter		
5	Digital Noise Reduction	3D DNR, WDR: 120dB or better		
6	Focal length	2.7 to 13.5 mm or better		
7	Aperture	F1.4 with Auto focus or better		

8	IR Range	50 m or higher		
9	Video Compression Main stream	3-Line, H.265+/H.265/H.264+/H.264/MJPEG		
10	Video Bit Rate	3 Kbps to 8 Mbps		
11	Audio Compression	G.711 / G.711mu/G.726/PCM/AAC		
12	S/ N ratio	> 56 dB		
13	Environment Noise Filtering	Yes		
14	Audio Sampling Rate	8kHz/16kHz/32kHz/44.1kHZ/48kHz		
15	Image Max. Resolution	2688 × 1520, 50Hz: 25fps		
16	Image Enhancement	BLC/3D DNR/HLC		
17	Image Setting	Rotate mode, saturation, brightness, contrast, sharpness adjustable by client software or web browser		
18	Day/Night Switch	Day / Night / Auto / Schedule / Triggered by Alarm In		
19	Alarm Trigger	Motion detection, video tampering, network disconnected, IP address conflict, illegal login, HDD full, HDD error, Alarm input, Alarm output; Alarm output Protocols: TCP/IP, ICMP, HTTP, etc		
20	Edge Analytics	line crossing, region entry / exit, intrusion, video blur, face capture, detection, etc		
21	Simultaneous Live View	Up to 6 channels		
22	User/Host	Up to 8 users, 3 levels: Administrator, Operator and User		
23	Interface	1 input (line in, 3.5 mm), 1 output(3.5 mm), single track / 1 RJ45 10M/100M self-adaptive Ethernet port / 1 input, 1 output (max. 12 VDC, 30 mA) / Built-in Micro SD/SDHC/SDXC slot, up to 512 GB / H.264 encoding supports		
24	Operating Temperature	-30 °C to +60 °C		
25	Power Supply	12 VDC, PoE (802.3af)		
26	Material	Metal		
27	Protection Level	IP67, Lightning Protection, Surge Protection and Voltage Transient Protection.		
28	REGULATORY	CE, FCC, ONVIF, BIS, STQC		

IP 4MP IR ANPR Camera with Varifocal lens				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Image Sensor	1/1.8" CMOS Sensor or better		
2	Min. Illumination	0.0001 lux or better		
3	Shutter Speed	1/25 s to 1/100,000 s or better		
4	Day & Night	IR Cut Filter		
5	Digital Noise Reduction	3D DNR, WDR: 140dB or better		
6	Focal length	10 to 50 mm or better		
7	Aperture	F1.2 or better		
8	IR Range	30 m or higher		

9	Video Compression Main stream	H.265, H.264M, H.264H, H.264B, MJPEG		
10	Video Bit Rate	32 Kbps to 32000 Kbps or better		
11	Audio Channel In/Out	1 each		
12	S/ N ratio	> 56 dB or better		
13	Image Max. Resolution	2688 × 1520, 25fps		
14	Image Enhancement	BLC/3D DNR/HLC		
15	Day/Night Switch	Day/Night/ Auto/Schedule/Triggered by Alarm In		
16	Alarm Trigger	Storage Full, Storage Error, External Alarm, No Storage card, Illegal Access, Vehicle Blocklist, IP Conflict, No Network		
17	Protocols	SFTP, IPv6, IPv4, DNS, RTCP, NTP, RTP, HTTP, HTTPS, SNMP V3, TLS Version 1.2, TCP/IP, etc		
18	Time Sync	NTP, GPS; Defog: Supported		
19	Edge Enhancement	Supported		
20	Security	AES (256) Encryption, Security Logs, Trust Execution, IP/MAC filtering, Video Encryption, HTTPS, Account Lockout, Trusted Upgrade and Boot		
21	Exposure	Auto/Manual		
22	Composite Image	Should Support		
23	Network Recovery	Should Support		
24	Interface	1 RJ45 10M/100M self-adaptive Ethernet port / 1 input, 1 output (max. 12 VDC; Built-in Micro SD/SDHC/SDXC slots Max Storage upto 512GB		
25	Operating Temperature	-40 °C to +65 °C		
26	Power Supply	12 VDC, PoE		
27	Material	Metal		
28	Protection Level	IP67, IK10		
29	REGULATORY	CE, FCC, ONVIF, BIS, STQC		

Network Video Recorder				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	IP Camera Input	8 Channels or higher		
2	Operating System	Embedded LINUX or Windows		
3	Audio Iuput/Output	1 Channel Input, 1 Channel Outputs		
4	Display Interface	1 HDMI & 1 VGA or higher		
5	Security	Face Detection, Recognition, Perimeter Protection, SMD Plus (all these features should support)		
6	Video Compression	H.265, H.264 or better		
7	Resolution support	2MP to 32 MP or higher		
8	Record Bit Rate	384Mbps incoming and outgoing or better		
9	Recording Mode	Schedule (Regular/Continuous, Motion Detection, Alarm), Manual, Stop		
10	Storage	Internal		
11	HDD	Minimum 2 SATA ports		

12	HDDs Capacity	Should support 10 TB or higher		
13	Sync Playback	1/4/8/16/32, Smart Search or better		
14	Playback Function	Play/ Pause/ Stop/ Rewind/ Fast play/ Slow play/ Next File/ Previous File/ Next Camera/ Previous Camera/ Full Screen, Instant, Event wise, Smart		
15	Audio Compression	G.711a, G.711u, G726, AAC		
16	Multi Channel Playback	Should support		
17	Network Port	Minimum 1 x RJ-45 port (10/100/1000Base-T Mbps)		
18	Supported Protocols	HTTP, HTTPS, TCP/IP, IPv4, UDP, NTP, DHCP, DNS, SMTP, UPnP, DDNS, Alarm Server, Multicast, P2P, iSCSI		
19	ONVIF	ONVIF Profile T, Profile S, Profile G, SDK,		
20	ANPR by Camera (Number of Channels)	Should support minimum 4 ANPR Camera or higher		
21	License Plate Database Capacity	Can be store minimum 20,000 or higher number plates.		
22	Black List & White List number plate featues	Number plate Black Listing & White Listing features should available		
23	Abnormality Alarm	Camera offline, Storage error, Disk full, IP conflict, MAC conflict, Login lock, Abnormal behaviour of fan, Cyber security exception		
24	Backup Mode	USB / Device Network		
25	Interface Ports	2 USB, 1 RS232, 1 RS485 or higher		
26	Operating Temperature	-10 °C ~ +55 °C or better		
27	Regulatory	CE, FCC, ONVIF		

Eligibility Criteria for Network Active (PoE Switches) OEM:

SL	Eligibility Criteria	Compliance with Document
1	OEM should have Service Centers in India in their own name. This is to be supported with documentary evidence.	
2	OEM should have valid ISO 9001:2015, ISO 14001:2015, ISO 14064-1:2018 & ISO 45001:2018 certified for their products, all the relevant certificates must be submitted along with the bid.	
3	Switch OEM company should not be technically rejected in any Govt. tender in WB for their origin from any land border sharing countries of India.	
4	The OEM must not be blacklisted or banned by any State/Central Government, Semi Government or PSU and any other GOVT. organization in INDIA and Globally.	
5	Certificate of Non-Obsolescence: OEM must provide a certificate that the proposed model of Network Switch products must not become obsolete /End of Life (EOL) within a period of 5 years, in case it gets EOL due to technology advancement then OEM will support with equivalent or higher model.	

Giga PoE Ethernet Switch				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	PoE Port	8 Nos. Giga Coper PoE 10/100/1000Mbps Ports		
2	Uplink port (Copper)	2 Nos. Giga Coper Uplink 10/100/1000Mbps ports or higher		
3	Uplink port (Fiber)	1 Nos. Giga SFP Uplink port or higher		
4	PoE Power Budget	150 Watt or higher		
5	Lightning Protection	Should available		
6	Switching Fabric	24 Gbps or better		
7	Date Transfer	Gigabit 1000Mbps		
8	Duplex	Full and Half		
9	MDI	Auto Flip and Self Negotiation		
10	Certifications	CE, RoHS		

Eligibility Criteria for Network Passive (Cables, Connector) OEM:

SL	Eligibility Criteria	Compliance with Document
1	The OEM must not be blacklisted or banned by any State/Central Government, Semi Government or PSU and any other GOVT. organization in INDIA and Globally.	
2	The OEM have their Own service center running & operational within India. Documentary evidence is submitted along with the bid.	
3	OEM should have valid ISO/IEC 27001: 2013 Certification. Certificate must be submitted along with the bid otherwise it may cause for rejection of bid.	
4	OEM should have Inventory of Green House Gas Emission verification certificate in accordance with ISO 14064-1: 2006. Certificate must be submitted along with the bid otherwise it may cause for rejection of bid.	

Outdoor CAT-6 UTP Cable				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Jacket	Double Jacket		
2	Type	Outdoor		
3	Pair	4 Twisted Pairs separated by internal X shaped		
4	Conductor Diameter	23AWG Solid Bare Copper or better		
5	Outer Sheath	UV-PE		
6	Insulation	High Density Polyethylene		
7	Operating Temperature	20°C to +60°C or better		
8	UV Resistant	Should available		
9	Compliant	ANSI/TIA, ISO/IEC, EN		

CAT-6 Patch Cord				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Pairing of cable	Twisted into 4 Pair		
2	Total No of Pairs	Four pair with twisted cable		
3	Colour Code	Orange-white with Orange, Brown – white with Brown, Blue – white with Blue, Green – white with Green		
4	Nominal Conductor Diameter	23 AWG or better		
5	Length	1 Meter		

RJ-45 CONNECTOR				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Support	4 Twisted Pair		
2	Housing	PC, UL94V-2		
3	Contact	Copper in Alloy or better		
4	Standard	T568A / T568B		
5	Operating temperature	-20^0C to 60^0C or better		

Surveillance Grade HDD				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Grade	Surveillance		
2	RPM	7200		
3	Storage	4 TB / 6 TB / 8 TB		
4	Cache Memory	64 MB or better		
5	Maximum Transfer Rate(OD)	190MB/s or better		
6	Load/Unload Cycle	300,000 or better		
7	MTBF	10,00,000 Hrs or better		
8	Idle. Average Wattage	<4 W or better		
9	Operating temperature	0^0C to 60^0C or better		

1 KVA Offline Uninterrupted Poser Supply with inbuilt Battery				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Capacity	1000VA		
2	Voltage Range	140~300VAC with ± 5% or better		
3	Frequency	50Hz		
4	Battery Type	SMF		
5	Power	12V 7AH, Auto Switch Off Mode with Low Battery		
6	Overload Protection	Should available		
7	Off Mode Charging	Should available		
8	Waveform	Modified Sinewave		
9	Operating Temperature	0^0C to 40^0C or better		

Outdoor Network Rack				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Type	Weather proof metallic box with accessories to accommodate power supply unit (PDU), MCB, NVR, Network switch, UPS etc.		
2	Size	12U X 550 X 500 (H X W X D)		
3	Door Type	Front Lockable Door with Lock		
4	Fan Unit	Supported		
5	Material	Powder Coated Galvanized Steel		
6	Provision of PDU	Supported		
7	Protection	IP 55 or better		
8	Top Cover	Rain and Dust Resistance		

17 Inch LED Display				
Sr. No	**Parameters**	**Minimum Technical Specification**	**Complied (Yes / No)**	**Remarks**
1	Resolution	HD 1366 X 768 or better		
2	Refresh Rate	60Hz		
3	HDMI Input	Yes		
4	Brightness	220cd/m² or better		
5	Color	16.7 M or better		
6	Aspect Ratio	16:9'		
7	Viewing Angle	H170° / V160° or better		
8	Ports	1 X HDMI, 1 X VGA		
9	Mounting	Wall		
10	Power Consumption	<20 W or better		

BODY WORN CAMERA				
Sl No	**Features**	**Details Specification**	**Complied (Yes/No)**	**Remarks**
1	Screen	2 inch 16:9 TFT LCD or better		
2	Angle of Lens	F2.0 Iris diaphragm, 130° wide angle or better		
3	Sensor	1/2.5 CMOS Color Sensor or better		
4	Video Frame Rate	30fps, 60fps or better		
5	Compression	H.264 or better		
6	Video Resolution	2304X1296 @ 30fps, 1920X1080 @ 30fps (1080p),1920X1080 @ 45fps, 1728x1296@30fps, 1420x1080@30fps, 1280x720@60fps, 1280X720 @ 60fps 1280X720 @30fps (720P), 848X480 @30fps (VGA), 320x240@QVGA		
7	Snapshot	21MP, 12MP, 10MP.8MP, SMP, 3MP, 2MP, VGA or better		
8	Auto Power Off	3min, 5min, 10min		

9	Storage	16 GB removable storage		
10	Storage Support	64GB or higher		
11	Recording Function	Video (MOV), Audio(WAV), Snapshot(JPEG)		
12	Recording Time	6 hrs or more at 720p		
13	Charging Time	shoule be less than 5 hrs		
14	Overwrite Function	Should be available		
15	Night Vision	10 meter or better		
16	Screen Saver	3min, 5min, 10min		
17	Battery Capacity	Built-in 3000mAh or better		
18	USB Interface	USB 2.0		
19	Flash Light	Should be available		
20	LED Indicators	Should be available		
21	Drop Test	1.8m or better		
22	Working Temperature	-30°C-60°C or better		
23	Working Humidity	< 93% or better		
24	Weatherproof Standard	IP 66 or better		
25	Password Protection	Features should available		
26	Single dock	Features should available		
27	Weight	Should be less than 100g (Body Worn Camera) & should be less than 20g (for back clip)		

Night Vision Binocular				
SL No	**Features**	**Details Specification**	**Complied (Yes/No)**	**Remarks**
1	Type	Digital Day & Night Vision Binocular (Dual Eye Viewing)		
2	Operation Mode	Color (Day) & Infrared / Black & White (Night)		
3	Sensor	CMOS digital sensor or better		
4	Display	Circular OLED / TFT display (Dual Eyepiece)		
5	Optical Magnification	Minimum 3X or better		
6	Digital Zoom	Minimum 8X or better		
7	Objective Lens Diameter	Minimum 25 mm or better		
8	Focus	Manual Focus with Diopter Adjustment ±3 or better		
9	Field of View	Minimum 13 degree or better		
10	Infrared (IR) System	Built-in Infrared Illuminator		
11	IR Levels	Minimum 3 Adjustable IR Levels		
12	IR Wavelength	850 nm to 940 nm		
13	Night Visibility Range	Minimum 500 meters (preferably up to 600 meters)		
14	Photo Resolution	Minimum 40 MP (interpolated acceptable)		
15	Video Resolution	4K UHD (interpolated acceptable)		
16	Video Format	MP4 / AVI or equivalent		
17	Photo Format	JPEG		
18	Date & Time	Date & Time Stamp on Photos and Videos		
19	Anti-Shake	Anti-Shake Feature preferred		
20	Tactical	Built-in Tactical White Light with Strobe Mode for Emergency Signaling		

21	Backlit Control	Backlit Control Buttons for Night Operation		
22	Tripod Mount Provision	Tripod Mount (Standard 1/4 inch thread)		
23	Ergonomic Rugged	Ergonomic Rugged Design suitable for prolonged field use		
24	Neck strap	Neck strap and protective lens caps		
25	Head Mounted option	Head Mounted option to be also provided with accessories.		
26	Battery	Rechargeable Removable Battery		
27	Battery Capacity	Minimum 3500 mAh or better		
28	Battery Backup	Minimum 8–12 Hours (without IR) or higher		
29	Charging Port	Type-C preferred		
30	Charging Support	Support charging through power bank		
31	Storage	External TF / Micro SD Card Support		
32	Capacity Support	4GB to 512GB minimum or better		
33	Connectivity	USB Data Transfer Capability should be there		
34	Memory Protected	Memory card slot protected against dust/moisture		
35	Environmental	Minimum IP 65 Protection Rating or better		
36	Protection Standards	Shock Resistant and Field Ruggedized Body		
37	Temperature	Operating Temperature Range: -10°C to +50°C or better		
38	Conditions	Suitable for Humid, Forest, Rainy & Dusty Conditions		
39	Standard	Rechargeable Battery		
40	Cable Type	Type-C Charging Cable		
41	Accessories	Data Cable		
42	Carrying Case	Hard/Soft Tactical Type		
43	Standard Accessories	Cleaning Cloth should be available		

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Stamp of the Company: _____

WEBEL TECHNOLOGY LIMITED

SECTION – S

MANUFACTURER'S AUTHORIZATION FORM

Date:

To
Webel Technology limited
Plot-5, Block-BP, Sector-V
Salt Lake
Kolkata-700 091

Ref: Tender No-WTL/WBPNB/CCTV/26-27/046 Dated 01-09-2026

WHEREAS _____ who are official producers of _____ and having production facilities at _____ do hereby authorize _____ located at _____ (hereinafter, the "Bidder") to submit a bid of the following Products produced by us, for the Supply Requirements associated with the above Invitation for Bids.

When resold by _____, these products are subject to our applicable standard end user warranty terms.

We assure you that in the event of _____, not being able to fulfill its obligation as our Service Provider in respect of our standard Warranty Terms we would continue to meet our Warranty Terms through alternate arrangements.

We also confirm that _____is our authorized service provider/system integrator and can hence provide maintenance and upgrade support for our products.

We also confirm that the products quoted are on our current product list and are not likely to be discontinued within from the day of this letter. We assure availability of spares for the products for the next two years after warranty period.

We also confirm that the material will be delivered within 30(thirty) days from the date of placement of confirmed order.

Name In the capacity of

Signed

Duly authorized to sign the authorization for and on behalf of _____

Dated on _____ day of_____2026

Note: This letter of authority must be on the letterhead of the Manufacturer and duly signed by an authorized signatory.

WEBEL TECHNOLOGY LIMITED

SECTION – T

CHECKLIST FOR ELIGIBILITY CRITERIA

(Tender No.)

Sl. No.	Eligibility Criteria	Compliance (Yes / No)	Documents Attached at Page No of Technical Bid
1.	The bidder must be a company registered under Companies Act, 1956/2013 or Partnership or LLP or OPC or Proprietary Firm. Documentary (Certificate of incorporation/Relevant document) evidence to be submitted.		
2	The bidder must be a System Integrator in IT/ITS or Audio Video sector. Relevant document to be submitted.		
3	The bidder should have been operating for the last 5 years in India. Certificate of Incorporation and/ or Certificate of Commencement of Business issued by the Registrar of Companies/ Partnership Registration/ sole proprietorship registration under the Shops & Establishments Act to be submitted.		
4	The bidder must have their Registered/ Branch office in West Bengal. Valid trade license and local GST Registration Certificate are to be submitted.		
5	The bidder should have valid GST Registration Certificate & PAN. Bidder shall have to submit photocopy of the documents.		
6	Bidder should have own support service / call booking number (Undertaking letter should be submitted from the bidders) OEM support service number will not be treated as bidder's support service number. Support service number details for bidder with number & detailed to be submitted. Bidder shall have to submit the Complain/Call escalation matrix in their own letterhead with undertaking.		
7	The bidder shall have executed "Similar Nature" of **single order an amount** not less than **Rs. 6.40 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided. **OR** The bidder shall have executed "Similar Nature" of **two orders, each amount** not less than **Rs. 4.00 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided. . **OR** The bidder shall have executed "Similar Nature" of **three orders, each amount** not less than **Rs. 3.20 Crore** in last 05 (Five) financial years (considering FY – 2021-22, 2022-23. 2023-24, 2024-25, 2025-26) in Government Department/PSU/Autonomous Body. References order copy with the completion certificate for the project to be provided.		
8	The bidder should have a minimum **average annual turnover** of not		

	less than Rs. **12.00 Crore** in the last three financial year (2022-23. 2023-24, 2024-25). Bidder shall have to submit Audited Balance Sheet / Audited Accounts / Auditor Certificate in support of their claim.		
9	Bidder should have Positive net worth for last three financial years (2022-23. 2023-24, 2024-25). Bidder shall have to submit Audited Balance Sheet / Audited Accounts / Auditor Certificate in support of their claim.		
10	The bidder should have ISO certification of ISO 9001:2015. Certificate to be submitted.		
11	The bidder must submit the Manufacturers Authentication Form (MAF) for IP Based CCTV, Networking Switches & Network Passive component as per prescribed format enclosed (Section - S).		
12	Technical Compliance statements to be submitted. Without these documents from the OEMs, the offer will be treated as non-responsive and summarily rejected.		
13	The bidder shall submit Bid Form (Section – E) duly signed by the authorized signatory of the company as per the format enclosed. Deviation in format may not be accepted.		
14	Bidder shall submit NIT Declaration (Section – O) duly signed by the authorized signatory of the company as per the format. Deviation in format may not be accepted.		
15	The bidder shall not have been blacklisted by any State/Central Government or PSU Organization or bilateral/multilateral funding agencies for breach of ethical conduct or fraudulent practices as on date of submission of the proposal (as per DIT guidance note issued on 26-Dec-2011). Declaration on bidder's letter head to be submitted.		

Note: Bidder should clearly mention the page no or identification mark for contents of the document. The document submitted should mention all their respective submission as per RFP with proper page no. or identification marking

Authorized Signatory (Signature In full): _____

Name and title of Signatory: _____

Company Rubber Stamp: _____

Signature Not Verified

Digitally signed by ANIRUDDHA GHOSH
Date: 2026.09.01 14:54:30 IST
Location: West Bengal-WB